

British Rail Property Board, 2001/02 Bedfordshire County Council

Southill Road Railway Bridge
No. HIB27

Assessment Report

Our ref Please reply to Direct Dialling No E-mail Address



Your ref

9th July 2003

Mr British Railways Board (Residuary) Ltd Rail Property Ltd Hudson House YORK Y01 6HP





c/o Babtie Group PO Box 272 The Merton Centre 45 St. Peter's Street Bedford MK40 2ZY

Tel: 01234 763400 Fax: 01234 763401



ASSESSMENT OF BRB BRIDGES IN BEDFORDSHIRE SOUTHILL ROAD RAILWAY BRIDGE (HIB27) AMENDED ASSESSMENT

We have now completed our re-assessment of HIB27 as discussed at our meeting of 25th June 2003.

As expected, the use of the revised joint depth factor has increased the allowable single axle load to 9.0 tonnes. The assessed capacity of the bridge is now 13 Tonnes (12.5T GVW).

As previously agreed at our meeting I enclose the following revised pages for incorporation into your copy of the previous report.

- Page Nos 1, 2, 4, 6 & 7 of the assessment report
- Amended Form BA (2 pages)
- Amended Form BAA (2 pages)
- Amended calculation pages 5, 6, 6a, 10 & 15.

I look forward to receiving a copy of the countersigned Forms BA and BAA in due course.

Yours sincerely



DOCUMENT ISSUE RECORD

Document	Status	Issued to	No. of	Date of issue	Signed
Form AA	Final	Rail Property Ltd	1	1/05/2002	
Assessment Report	Final	Rail Property Ltd	1	28/10/02	MY
Assessment Report	Final	Beds CC	1	11/11/02	MY
Assessment Report Revised pages	Final	Rail Property Ltd	1	9/7/03	824
Assessment Report Revised pages	Final	Beds CC	1	9/7/03	ae7
			·		
			: -		

Copyright Babtie Group Limited. All rights reserved.

No part of this report may be copied or reproduced by any means without prior written permission from Babtie Group Limited. If you have received this report in error, please destroy all copies in your possession or control and notify Babtie Group Limited.

This report has been prepared for the exclusive use of the commissioning party and unless otherwise agreed in writing by Babtie Group Limited, no other party may use, make use of or rely on the contents of the report. If others choose to rely upon this report they do so entirely at their own risk. No liability is accepted by Babtie Group Limited for any use of this report, other than for the purposes for which it was originally prepared and provided.

Opinions and information provided in the report are on the basis of Babtie Group Limited using due skill, care and diligence in the preparation of the same and no explicit warranty is provided as to their accuracy. It should be noted and it is expressly stated that no independent verification of any of the documents or information supplied to Babtie Group Limited has been made.

Contents

-	<u>SECTION</u>	<u>TITLE</u>	<u>Page</u>
_		Document Issue Record	1
_		Synopsis of Assessment Results	2
-		Contents	3
-	1.0	Introduction	4
	2.0	Assessment	4
=	2.1 2.2	Assessment of Brick Arch Assessment of Substructure and Foundations	4 4
-	3.0	Design Parameters and Material Strengths Used in the Assessment	4
-	3.1 3.2 3.3	Factors used for Modified MEXE Method Arch Profile Additional Information	4 4 5
-	3.4	Assessment Loading	5
•	4.0 4.1 4.2	Assessment Results Structure Assessment Summary of Results Substructure & Foundations	6 6 7
-	5.0	Discussion of Assessment Results	7
-	6.0	Conclusions	7
•	APPENDICES		
-	APPENDIX A	Approval in Principle	
_	APPENDIX B	Assessment and Check Certificate	
	APPENDIX C	Assessment Calculations	
-	APPENDIX D	Assessment Inspection Report	

SYNOPSIS OF ASSESSMENT RESULTS

Arch Assessment

The Assessment Capacity of the Bridge is 12.5 Tonnes GVW (13 Tonne Restricted Live Loading) with no restriction to Fire Engine Group 2.

1.0 Introduction

1.1 Structure Details

Bridge name

Southill Road Bridge

Bridge no.

Rail: HIB 27 BCC U147/9027

OS reference

TL 0907 4689

1.2 Structure Description

The bridge carries the U147 Southill Road over a disused railway and is located 1 km south of Cardington village. The date of construction is not known, but possibly built in 1855 as other bridges on the same line.

The bridge is a single span four ring brick arch supported on brick abutments. The wingwalls, spandrels and parapets are of brick. The foundations are assumed to be spread footings. The Bridge has a skew of 21 degree.

2.0 Assessment

2.1 Assessment of Brick Arches

The assessment of the arch has been carried out using the Modified MEXE Method, and the capacity has been confirmed, using the ARCHIE computer program.

The assessment is based upon the AA form dated 28th April 2002, prepared by the Babtie Group on behalf of Bedfordshire County Council. Centrifugal effects have been ignored in the assessment as the road is of straight alignment over the structure. Axle-lift off has been considered in the assessment because of the humped vertical curve over the structure.

2.2 Assessment of Substructure and Foundations

The abutments and wing walls have been assessed qualitatively in accordance with Chapter 8 of BD 21/01.

3.0 Design Parameters and Material Strengths used in the Assessment

The following parameters and material strengths (as stated in the Principle Inspection report, Appendix F) have been used in the assessment.

3.1 Factors used for modified MEXE method and ARCHIE collapse mechanism method

The following factors have been determined from the assessment inspection and used in the MEXE and ARCHIE assessments of each arch:

Barrel Factor F _b	1.0	
Fill Factor F _f	0.7	
Joint Width Factor Fw	0.9	
Mortar Factor F _{mo}	1.0	
Joint Depth Factor F _d	0.9	(As bottom ring ignored, F _d taken as 1.0)
Condition Factor Form	0.6	

No record drawings are available for the structure, which state type of brickwork and mortar used.

3.2 Arch Profile

The inspection has identified that there is longitudinal cracking, seepage deposit and areas of hollow sounding brickwork in the arch intrados. Therefore a barrel with thickness of 3 rings has been used in the assessment as it is assumed the lower (fourth) ring is ineffective due to ring separation.

3.3 <u>Additional information</u>

Additional information was obtained from the following drawings, which are contained in Appendix B and D of the Assessment Inspection Report.

Drg. Nos.	Drawing Description
HIB27/1	Plan And Levels
HIB27/2	East Elevation
HIB27/3	West Elevation
HIB27/4	Cross Sections 1
HIB27/5	General Arrangement
HIB27/06	Elevations Defects
HIB27/07	Arch Defects
HIB27/08	Abutment Defects
HIB27/09	Carriageway Defects

3.4 Assessment Loading

The structure has been assessed for the 40/44 tonne assessment live loading in accordance with the Approval in Principle document.

4.0 Assessment Results

4.1 Structure Assessment Summary of Results:

Structure Name: SOUTHILL ROAD BRIDGE	HIB 27 BCC U147/9027	
MODIF	ED MEXE ANALYSIS	
ASSESSMENT LIVE LOADING	IED WEXE ANALTOIO	
Allowable gross Axle Weight:	Axle weight	Capacity
Single axle	9.03 T	12.5 T GVW
Double axle bogie (lift off)	4.37 T	-
Triple axle bogie	5.25 T	-
CAPACITY	12.5 Tonnes GVW (13 Tonn Restriction to Fire Engine G Table F1 – Bl	roup 2 (From ANNEX F.

Structure Name: SOUTHILL ROAD BRIDGE	HIB 27 BCC U147/9027	
ARCHIE	ANALYSIS	
ASSESSMENT LIVE LOADING	PASS/FAIL	
Single Axle 10.5t (33-17t Restriction)	Fail	
Double Axle 18t (25t Restriction)	Fail	
Single Axle (13t Restriction)	Fail	
Single Axle (10t Restriction)	Fail	
Single Axle (7.5t Restriction)	Fail	
Single Axle (3.0t Restriction	Pass	

The following boxes are NOT to be completed by the Consultant unless authorised to do so by the Employer's Representative.

SI 1705 (1972) Loading		
Pass / Fail		

4.2 Substructure and Foundations

The abutments and the walls were assessed visually during the assessment inspection in accordance with Chapter 8 of BD 21/01. There are a number of hairline cracks in both north and south abutment walls, which may appear to be due to movement/settlement of foundations. However it is considered that the condition factor of 0.6 has taken this into account in the assessment of the arch.


There are a number of defects such as areas of poor joints, surface spalling, hollow brickwork, bulging and cracks to both south-east and south-west wingwalls. Whilst there is no evidence of failure of the walls due to rotation or forward movement, the above mentioned defects do give cause of concern. The walls are accordingly considered to be inadequate by inspection until such time as the defects are repaired, and the walls proven adequate by calculation. As the thicknesses of the walls and dimensions of their foundations, and ground conditions are unknown, an extensive site investigation would need to be carried out prior to any proposed analytical assessment.

5.0 Discussion of Assessment Results

- 5.1 The assessment of the arch using the Modified MEXE Method indicates that it is capable of carrying vehicles of 12.5 T GVW (13 tonne restricted live loading) with no restrictions to Fire Engine Group 2.
- 5.2 A collapse mechanism analysis was carried out using the computer program ARCHIE in order to confirm the capacity of the arch. It gave a result of 3.0 tonnes. Therefore, in accordance with Clause 6.19 (i) in Chapter 6 of BD21/01, the capacity of 12.5 tonnes GVW calculated by the Modified MEXE Method shall be taken.
- Ignoring the bottom ring in the assessment may be considered overly conservative. A sensitivity analysis was carried out in order to determine whether using 4 ring thick arch barrel and reducing the condition factor from 0.6 to 0.4 would significantly affect the results. The Capacity of the structure using modified MEXE method appears to lie between 10 and 18 tonnes depending upon the condition factor and number of rings used.
- 5.4 Investigation to determine the extent of ring separation is likely to prove inconclusive and is therefore not considered to be cost effective. Strictly in accordance with AIP, the capacity of the structure is 12.5 tonnes.

6.0 Conclusions

6.1 The overall carrying capacity of the structure is <u>12.5 tonnes</u> GVW (13T Live Load Restriction) with no restrictions to Fire Engine Group 2.



APPENDIX A

Approval in Principle

Group Standard

FORM 'AA' (BRIDGES)

GC/TP0356

Appendix: 4

Issue: 1 Revision: B (Nov 2000)

ELR/ Bridge No HIB 27

APPROVAL IN PRINCIPLE FOR ASSESSMENT

Bridge/Line Name

Southill Road Railway Bridge

ELR/Bridge No.

HIB 27

Brief Description of Existing Bridge:

(a) Span Arrangement .

Single span masonry arch with skew span of 8.575 metres

(b) Superstructure Type

Square spanning single span brickwork arch. Voussoirs indicate a 4 ring arch 2 bricks thick.

(c) Substructure Type

Brickwork abutment, spandrels and wing walls.

(d) Details of any Special Features

None

Assessment Criteria

(a) Loadings and Speed

40/44 Tonne assessment loading of BD21/01.

There is no specific speed restriction on the road over the bridge. Therefore the general speed limit of 60mph (97 kph) for single carriageway roads applies.

(b) Codes to be used

RT/CE/P/010 (Issue 2-Dec 1997) Technical Approval Procedures for Assessment of Bridges and Other Structures.

BD21/01 The Assessment of Highways Bridges and Structures BA16/97 The Assessment of Highways Bridges and Structures (Advice Note)

BA55/00 The Assessment of Bridge Substructures and Foundations, Retaining Walls and Buried Structures (Advice Note)

Group Standard

FORM 'AA' (BRIDGES)

GC/TP0356

ELR/ Bridge No HIB 27

Appendix: 4 Issue: 1

Revision: B (Nov 2000)

APPROVAL IN PRINCIPLE FOR ASSESSMENT

(c) Proposed Method of Structural Analysis

(d) Details of any Special Requirements

None

Category 1

The structure will be assessed initially using the Modified MEXE method. The inspection indicated large areas of hollow sounding brickwork. Accordingly it is proposed that the arch is assessed as consisting of 3 rings rather than 4. If the depth of fill over the arch exceeds the arch ring thickness then the depth of fill will be restricted to this lesser value in the calculations. If the capacity of the arch is below the 40/44 Tonne assessment level then the arch capacity will be confirmed using the ARCHIE computer program. (see Cl. 6.17 of BD21/01). Abutments and wingwalls will be assessed qualitatively in accordance with BD21/01 and BA55/00.

Senior Civil Er	ngineer's	Comment	s			
		N	One		• • • • • • • • • • • • • • • • • • • •	
Superstr	ucture	1 .	÷			
Substruc	ture	1				
Name Of	f Checker	Suggested	If Cat 2 Or	3		

The above assessment, with amendments shown, is approved in principle:

Signed

Title

Date

BRB (Residuary) Limited Group Standard

FORM 'AA' (BRIDGES)

GC/TP0356

ELR/ Bridge No HIB 27

Appendix: 4 Issue: 1

Revision: B (Nov 2000)

APPROVAL IN PRINCIPLE FOR ASSESSMENT

Cate	gory	2 and	13
------	------	-------	----

The .	ahova	accessment	with	amendments	shown	is	approved	in	princir	nle:
ine a	above	assessment.	WILLI	anienuments	SHOWH.	ાગ	approved	11.6		, סוע

Signed	
Title	
Date	
Signed	
Title	
Date	

Group Standard

FORM 'AA/1' (BRIDGES)

GC/TP0356

Appendix: 4

Issue: 1 Revision: B (Nov 2000)

ELR/ Bridge No

HIB 27

APPROVAL IN PRINCIPLE FOR ASSESSMENT

Additional Information Required For BRB (Residuary) Limited Owned Public Road Overbridges Assessed As Part Of Bridgeguard III

Bridge/Line Name .

Southill Road Railway Bridge

ELR/Bridge No.

HIB 27

Scope Of Assessment

Assessment of ability of the structure to carry current

highway loading

Assessment Criteria

(a) Standards And Codes Of Practice To Be Used In Assessment

RT/CE/P/010 (Issue 2-Dec 1997) Technical Approval Procedures for Assessment of Bridges and Other Structures.

BD21/01 T

The Assessment of Highways Bridges and Structures

BA16/97 -

The Assessment of Highways Bridges and Structures (Advice

Note)

BA55/00 The Assessment of Bridge Substructures and Foundations,

Retaining Walls and Buried Structures (Advice Note)

(b) Proposed Method Of Structural Analysis

The structure will be assessed initially using the Modified MEXE method. The inspection indicated large areas of hollow sounding brickwork. Accordingly it is proposed that the arch is assessed as consisting of 3 rings rather than 4. If the depth of fill over the arch exceeds the arch ring thickness then the depth of fill will be restricted to this lesser value in the calculations. If the capacity of the arch is below the 40/44 Tonne assessment level then the arch capacity will be confirmed using the ARCHIE computer program.(see Cl. 6.17 of BD21/01). Abutments and wingwalls will be assessed qualitatively in accordance with BD21/01 and BA55/00.

- (c) Planned Highway Works/Modifications At This Site
 None
- (d) Road Designation Class And Whether Classed As A Heavy Load Route Unclassified county road. Not a Heavy Load Route.

Group Standard

FORM 'AA/1' (BRIDGES)

GC/TP0356

Appendix: 4

ELR/ Bridge No

HIB 27

Issue: 1

Revision: B (Nov 2000)

APPROVAL IN PRINCIPLE FOR ASSESSMENT

(e) Any Other Requirements
None

The Above Is Agreed Subject To The Amendments And Comments Shown


Below.

Signed

Title

For And On B

Date



APPENDIX B

Assessment and Check Certificate

FORM 'BA' (BRIDGES)

GC/TP0356

Appendix: 4

Issue: 1 Revision: A (Feb 1993)

ELR/ Bridge No HIB/27

CERTIFICATION FOR ASSESSMENT CHECK

Assessment Group: Babtie Group, on behalf of Bedfordshire County Council

Bridge/Line Name:

Southill Road Railway Bridge

Category Of Check:

Category 1

ELR/ Bridge No

HIB27

I certify that reasonable professional skill and care have been used in the assessment of the above structure with a view to securing that:

- (1) It has been assessed in accordance with the Approval in Principle (where appropriate) as recorded on Form AA approved on 3rd May 2002.
- (2) It has been checked for compliance with the following principal British Standards, Codes of Practice, BRB (Residuary) Limited Technical notes and Assessment standards.

List any departures from the above, and additional methods or criteria adopter reference and justification for their acceptance (commenting on the results if appropriate).						

Category 1

Name Signature Date

Group Standard

FORM 'BA' (BRIDGES)

GC/TP0356

Appendix: 4

Issue: 1 Revision: A (Feb 1993)

ELR/ Bridge No HIB/27

CERTIFICATION FOR ASSESSMENT CHECK

Category 2 and 3 (Note: Category 1 Check Must Also Be Signed)

(a) Assessment

<u>Name</u>

<u>Signature</u>

<u>Date</u>

Assessor

Assessment Checker

Partner Of the Firm Of Consulting Engineers To Whom Assessor/ Checker Is Responsible

(b) Check

<u>Name</u>

Signature

Date

Assessor

Assessment Checker

Partner Of the Firm Of Consulting Engineers To Whom Assessor/ hecker Is Responsible

This Certificate Is Accepted By.....

20/8/2003

Group Standard

FORM 'BAA' (BRIDGES)

ELR/ Bridge No HIB/27

GC/TP0356

Appendix: 4

Issue: 1 Revision: A (Feb 1993)

CERTIFICATION FOR ASSESSMENT CHECK

Notification of Assessment Check

Assessment Group: Babtie Group, on behalf of Bedfordshire County Council

Bridge/Line Name:

Southill Road Railway Bridge

Category Of Check:

Category 1

ELR/ Bridge No

HIB27

The above bridge has been assessed and checked in accordance with Standards which are listed on the appended Form BA. A summary of the results of the assessment in terms of capacity and restrictions is as follows:-

STATEMENT OF CAPACITY

13 Tonnes with no restriction to Fire a) Engine Group 2.

Fails under dead loads (by inspection). b)

Critical member/s:

Arch Barrel. a)

South-east & South-west wingwalls. b)

Recommended Loading Restrictions

Temporary measures to be put in place in accordance with BA 79/98

Description of Structural Deficiencies and Recommended Strengthening



Group Standard

FORM 'BAA' (BRIDGES)

GC/TP0356

Appendix: 4 Issue: 1

ELR/ Bridge No HIB/27

Revision: A (Feb 1993)

CERTIFICATION FOR ASSESSMENT CHECK

Category 2 and 3 (Note: Category 1 Check Must Also Be Signed)

(c) Assessment

Name

Signature

<u>Date</u>

Assessor

Assessment Checker

Partner Of the Firm Of Consulting Engineers To Whom Assessor/ Checker Is Responsible

(d) Check

Name

Signature

Date

Assessor

Assessment Checker

Partner Of the Firm Of Consulting Engineers Whom Assessor/ecker Is Responsible

This Certificate Is Accepted By...

2018/20

APPENDIX C

Assessment Calculations

Client:

Bedfordshire County Council

Commission Title:

British Rail Property Board 2001/2

Bridge Title:

Southill Road Railway Bridge, Cardington, No. HIB27

File Title:

Assessment Calculations

File Ref:

080714

BAB1	TE		CALCUL	ATION	SHEET
OFFICE	BEDFORD	PAGE No.	INDEX	CONT'N PAGE No.	
JOB No. & TITLE	080714 - SOUTHILL RAILWAY BR	ORIGINATOR	MY	DATE	OCT 102
SECTION	ASSESSMENT CALL'S	CHECKER	ary	DATE	17/10/02

CALCULATION INDEX

Assassment Summary
Survey Data

1-2

MEXE Assassment

ARCHIE Assassment

7-10

ARCHIE Protouts

11-13

Arch Parameters

14

Sensitivity Analysis

BABTIE	G	ALCUL	ATION	SHEET
OFFICE BEDFORD	PAGE No.	SOMMARY	CONT'N PAGE No.	
JOB No. 80714 - SOUTHILL RAILWAY BR	ORIGINATOR	My	DATE	QT 02
SECTION ASSESSMENT CARC'S	CHECKER	AZY	DATE	17/14/02


ASSESSMENT SUMMARY

MEXE - 10 TONNES ARCHIE - 3.0 TONNES.

THE ASSESSMENT CAPACITY OF THE BRIDGE IS 10 TOUNES

BABTIE		CALCUL	ATION	SHEET
OFFICE BEDFORD	PAGE No.		CONT'N PAGE No.	
JOB NO. 080714 - SOUTHILL RAILWAY BR-CARDNGTON	ORIGINATOR	MY	DATE	28.080
SECTION MEXE ASSESSMENT	CHECKER	azy	DATE	17/10/12
ASSESSMENT OF MASONRY ARCH BRIDGE &	,		METHON	
3 ring thick arch barnel is used in the asses - Span (2): = East Elevation = West Elevation =	8-794 m	HP)		
:. L = <u>8.794 + 8.739</u> =	= 8:767	n		L= 8.76
(All dumensions measured off.	survey de	raining i	using	
(All dumensions measured off Autocati)-dry No. 41827/02 &	#1627/0	3 See P	yes 283	
- Rise of the arch barrel at	the Crow	en Te	•	
East Elevation = 1.993 n = West Elevation = 1.989 n	1-993 + 1-98 2	9 = 19	19/~	[c = 1.99] (m)
- The Rise of the arch barrel of the West Elex East Elev	ie quarter	points ((7g):	
1.573 1.872	1.580 +1.57	73 + 1-568 4	5+1.572	rq = 1.573 (m)
- Thickness of the arch barnel adjac	ent to the 1	key ston	e (3	
Rug)"d" = 0-360 m		•	-	

-



BABTIE	C	CALCUL	ATION	SHEET
OFFICE ZARGARO	PAGE No.	4	CONT'N PAGE No.	
JOB No. 080714 - SOUTHILL PAILMAY BR - CAPLINGTEN	ORIGINATOR	MY	DATE	37.00.00
SECTION MEXE ASSESSMENT	CHECKER	azy	DATE	17/10/02
Average depth of full (h) = $0.673 + 0.708$	<u> </u>	, (ng yorel = 0.571	
d+h measured off Dry H1827/02		_		
:. h = (d+h)-d => 0				
h= 0-21	l m			h = 0.2
Provisonal axle loading (F	AL)			
$PAL = \frac{740 (d+h)^2}{L^{1.3}}$				
$PAR = \frac{740 (0.360 + 0.2)}{8.767}$	211)2		:	
PAL = 14.348 To	whes			PAL =
				14.348 TONIAL
MODIFYING FACTORS				
- Span/Rise Factor (Fsr):				
For = 4/1c > 8:	767/1.991	= 4.4	03	
As 4.403 > 4.000, the For from	n Fig 3/3	3 = 0.9	4	For=0:
- Profile Factor (Fp)				
Fp = \[\frac{1}{9} / \frac{1}{573}	1.99/ =	= 0.79	_6. (
0.79 7 0.75 : Fp = 2.3 \[\rac{\rac{\rac{\rac{\rac{\rac{\rac{\	=> 2.3	1.99/ - 1.	573	Fp= 0.9

0.90

BABTIE	C	ALCUL	ATION	SHEET
OFFICE SEDFOND	PAGE No.	5	CONT'N PAGE No.	
JOB NO. 80714 - SOUTHILL RAILWAY BR-CARDINIGTON	ORIGINATOR	MY	DATE	28.08.02
SECTION MEXE ASSESSMENT	CHECKER	azz	DATE	17/10/02
Condition Factors (from Assess.) $F_{b} = 1.0$ $F_{w} = 0.9$ $F_{mo} = 1.0$ $F_{cm} = 0.0$	·7 ·6 (Du to Cracker	lang ituo	-	984 zs/i/o
Fm = 0.89		•		Fm = 0.89
joint Factor (Fj)				
fj = Fwxfd x Fm fj = 0.9 x 0.9 x 1.0		BT 0.9	ž.	0.9 Fj = 0.81 UST 25/6/
Modified axle load = For x Fp x Fm x 5: = 0.94 x 0.90 x 0.89 x 0.8 = 5.250 (7) = 5.83 T	-			ae4
Ascle life off assumed due to	to hunp	backed		25/483

BABTIE		CALCUL	ATION	SHEET
OFFICE BED FORD	PAGE No.	6	CONT'N PAGE No.	6a
JOB NO. 80714 - SOUTHILL RAILWAY BR-CARDING	ORIGINATOR	MY	DATE	28.08.02
SECTION MEXE ASSESSMENT	CHECKER	art	DATE	17/10/02
				17

Allowable axle loads: (Lift-off)

Single Axle: $5.250 \times 1.55 (Fig 3/5a) = 8.136(7)$ 2 Axle begie: $5.250 \times 0.75 (Fig 3/5a) = 3.436(7)$ 3 Axle begie: $5.250 \times 0.90 (Fig 3/5a) = 4.725(7)$ 3 Axle begie: $5.250 \times 0.90 (Fig 3/5a) = 4.725(7)$

MAX GROSS VEHICLE WEIGHT = # TONNES

(ANNEX F, Table F1)

8D 21/01

25/6/03,

Pg 69 BEX 25/6/03.

MEXE ASSESSMENT Check Spreadsheet

Project:

80714

Structure:

Southill Road Railway Bridge HIB27 (With bottom ring ignored due to ring seperation) Sheet No.

MEXE Analysis to BA 16/97 (With axle lift-off)

L = 8.767

 $r_c = 1.991$ $r_g = 1.573$ d = 0.36

h+d = 0.571

Adjustment to limit h+d to 2*d not required 1

 $F_{b} = 1$

 $F_f = 0.7$

 $F_{w} = 0.9$ $F_{mo} = 1$

Taken as 10

Clause No:

3.10)

as bother ring being ignored. Provisional Axle Load = $740(d+h)^2/L^{1.3}$ = 14.35 tonnes

Span/Rise Factor $L/r_c = 4.40$ 3.11)

Hence $F_{sr} = 0.94$ (Fig 3/3)

Profile Factor $F_p = 2.3((r_c - r_q)/r_c)^{0.6} =$ 3.12)

Material Factor $F_m = ((F_b * d)+(F_f * h)) / (d+h) =$ 0.89 3.13)

Joint Factor $F_i = F_w * F_d * F_{mo} =$ 3.16)

Modified Axle Load = $F_{sr} * F_p * F_m * F_i * F_{CM} * PAL =$ tonnes 5.83 3.24)

Af for 2 axle bogie = 0.75With axle lift - off: Fig's 3/5a and 3/5b 3.27)

> 9.0 Allowable Axie = tonnes Single Axle $A_f =$ 1.55 a)


> 4.0 tonnes 2 Axle bogie $A_f =$ 0.75 Allowable Axle = b)

From Table 3/6 Max Gross Vehcle Weight = 12.5 tonnes

BABTIE	(ALCUL	ATION	SHEET
OFFICE BEDFORD	PAGE No.	7	CONT'N PAGE No.	
JOB NO. 80714 - SOUTHILL RAILWAY BRIDGE	ORIGINATOR	MY	DATE	02.09.02
SECTION ARCHIE ASSESSMENT	CHECKER	AEF	DATE	17/10/02

MEXE Results to be checked on ARCHIE

ARCH PROFILE



Arch Co-ordinates

0,0

1096 , 1051

2192 , 1584

3288 , 1882

4384 , 1991

5479 , 1886


6575 , 1567

7671 , 989

8767, 0

BABTIE	C	ALCUL	ATION	SHEET
OFFICE BEDFORD	PAGE No.	8	CONT'N PAGE No.	
JOB NO. 080714 - SOUTHILL RAILYVAY BR - CARDINGTON	ORIGINATOR	MA	DATE	30.08.02
SECTION ARCHIE ASSESSMENT	CHECKER		DATE	

- Span (L): 8.767 m
- Rise (12) = 1.99/ m
- Road profile obtained from elevation drawings.





Dinersians in mn

shength not necessary as 4th rung is ignored

in assessment

BABTIE	C	ALCUL	ATION	SHEET
OFFICE BEDFORD	PAGE No.	9	CONT'N PAGE No.	
JOB NO. 080714 - SOUTHILL RAILWAY BR - CARDINGTON	ORIGINATOR	MY	DATE	02.09.02
SECTION ARCHIE ASSESS MENT	CHECKER	027	DATE	17/10/02





Wheel spread = 300 + 211x32 = 511 mm. C/way width = 4.650 (m) - (AIP)

Longitudual Crack approx in the center of chuoy, it only one nethods can be positioned on the budge.

Effective Barrel width = 1.5+h => 1.5+0.211 = 1.711 m


EH Barnel W/2 (NO of wheels) - 1.711/2 > 0.856m

Actual Axle load w = 1.8 + 0.511 = 2.311m


Effective Barnel width = 2.311 + (0.856-0.511) = 2.912m

.. use load spread of 3.0 m

BABTIE		CALCU	LATION	SHEET
OFFICE BEDFORD	PAGE N	o. /ð	CONT'N PAGE No.	
JOB NO. 80714 - SOUTHILL ROAD RAILWAY	SR ORIGINA	ATOR MY	DATE	27. 29.02
SECTION ARCHIE ASSESSMENT	CHECK	ER AST	DATE	17/10/02
Archie data tiles: SIBRI		,		
Archie Printouts: Commission	on Folder A	ssessments/	H1B27	
Load Spread of 3.0 m Wa	s used in	Archie A	rsessmend	The state of the s
Archie Rosults	Reg ring thicke	ess Pa	-SS FAIL	
1. Single Axle 10.5(7) (33-17 + restrict)	537		FAILS	The course of th
2. Double Axl 18(T) (25 t Restriction)	\$77		FAILS	
3. Single Aule 13 T Restriction	496	: #	FAILS	
4. Single Axle 10 T Restriction	432	1	FAILS	a company of the comp
5. Single Axle 7.5T Restriction	390	Ŧ	AILS) { ?
6. Single Axle 3.0 T Restriction	230	(see Archi	ASSES:	ł-s
ASSESSMENT RESULTS	10 5	(see Archi attached a AAOS - A	A01)	Average Averag
MEXE	· ·	TONNES		ast
ARCHIE		TONNES		25/6/03
". According to B. MEXE assessme	D21/97 (6.1 nt shell	9(i)), mo Stand.	defied	
CAPACITY OF STRUCTURE	12.2			1




FAILS




FAILS

Bedford 080714 BRPB Assessments HIB27 Southill Road Railway Bridge Page: 12
Originator: MY Sep'02
Checker: AET 17/10/02




FAILS




FAILS

Page: 13
Originator: MY Sep'02
Checker: AST 17/10/02



FAILS



PASSES

Bedford 080714 BRPB Assessments HIB27 Southill Road Railway Bridge Arch Parameters

14

Page: 14
Originator: MY Sep'02
Checker: Alt 17/10/02

Span Depth of fill Ring depth Position of backing	8767 mm 220 mm 360 mm 0	Rise Depth of surfacing Ring depth factor Depth of mortar loss	1991 mm 100 mm 1 0 mm
Fill density Surfacing density	20 kN/m^3 22 kN/m^3	Masonry Density	21 kN/m^3
Phi for fill	30 deg	Masonry strength	2.5 N/mm^2
	Cia da Anta 21	restriction) at 7000	

Southill

Single Axle 3t restriction) at 7000 3000mm Load Lane width Required ring depth 1.67 88 kN/m Geometric F.O.S H Right 216 mm 82 kN/m 117 kN/m H Left 135 kN/m **V** Right V Left .33 Comp. zone at hinge 2 53 mm Factor on pass, press.

Hinges 4 AT 21 2 AT 11 3 AT 16 1 AT 2

Param(m	n).segment			_		
•	Stone	Vertical	Horizontal	Vertical	Horizontal	Additional
	Weight	Dead Load	Deadload	Live Load	Live Load	Pass Press
1	-3.8	-14.2	7.5	0	0	0
2	-3.9	-12.6	6.3	0	0	1.3
2 3	-3.9	-11.2	4.7	0	0	1.8
4	-3.9	-9.7	3	0	0	1.6
5	-3.9	-8	1.8	0	0	1.2
6	-3.8	-6.2	1.1	0	0	.8
7	-3.8	-4.9	.7	0	0	.6
8	-3.9	-3.8	.4	0	0	.4
9	-3.9	-3	.2	G	0	.2
Ī0	-3.9	-2.6	.1	0	0	.1
11	-3.9	-2.5	0	0	0	0
12	-3.9	-2.9	2	0	0	0
13	-3.9	-3.6	-,4	0	0	0
14	-3.9	-4.7	7	-2.1	2	0
15	-3.9	-6.1	-1.2	-7.8	-1	0
16	-3.9	-7.8	-1.9	-8.7	-1.4	0
17	-3.9	-9.6	-3	-3.6	8	0
18	-3.9	-11.2	-4.5	2	1	0
19	-3.8	-12.7	-5.9	0	0	0
20	-3.8	-14.5	-7.1	0	0	0

BABTIE	C	ALCUL	ATION	SHEE.
OFFICE BEDFORD	PAGE No.	15	CONT'N PAGE No.	
JOB No. 080714 - SOUTHILL RAILWAY BR	ORIGINATOR	My	DATE	QT'02
SENSITIVITY ANALYSIS	CHECKER	art	DATE	17/10/02

Ignoring the bottom ring may be considered overly consenable, accordingly further assessment with 4 rings is carried out Sensitivity Analysis to determine whether 4 ring thick arch bornel would increase Capacity.

L = 8.522m Fb = 1.0 Fc = 1.951m Ff = 0.7 Fq = 1.540m Fw = 0.9 d = 0.480 Fmo = 1.0 h+d = 0.691 Fd = 0.9

See attached spreadsheet on lege 16 Following.

The ownall Capacity increases to 18 Tonness. A reduced
The overall condition factor of One is possibly too high. A reduced
Figure will be used to find the sensitivity of the standard to this
portangles.

The overall capacity bearing to Some 10 Tonness 26/6/6

See attached MEXE check Spread Steets.

... The Capacity of the Structure is governed by the assumed rung Seperation

The capacity of the structure appears to he between 10 &18 tonnes depending upon number of surge used and condition factor.

Strictly in accordance with the ATP. He a care it is \$10 Tonnes.

(187) 26/6/0

For dimensions see pages 18219.

Sensitivity Analysis

4 rug thick arch barrel -480mm

Project:

80714

Structure:

Southill Road Railway Bridge HIB27

Sheet No.

2

MEXE Analysis to BA 16/97 (With axle lift-off)

L = 8.522

 $r_c = 1.951$ $r_q = 1.54$ d = 0.48

h+d = 0.691

Adjustment to limit h+d to 2*d not required 1

 $F_b = 1$

 $F_f = 0.7$ $F_w = 0.9$

 $F_{mo} = 1$ $F_{d} = 0.9$ $F_{CM} = 0.6$

Clause No:

Provisional Axle Load = $740(d+h)^2/L^{1.3}$ = 21.80 3.10)

Span/Rise Factor $L/r_c = 4.37$ 3.11)

Hence $F_{sr} = 0.94$ (Fig 3/3)

Profile Factor $F_p = 2.3((r_c - r_q)/r_c)^{0.6} =$ 3.12)

Material Factor $F_m = ((F_b * d)+(F_f * h)) / (d+h) =$ 0.91 3.13)

Joint Factor $F_j = F_w * F_d * F_{mo} = 0.81$ 3.16)

Modified Axle Load = $F_{sr} * F_p * F_m * F_j * F_{CM} * PAL =$ 8.21 tonnes 3.24)

Af for 2 axle bogie = 0.75 With axle lift - off: Fig's 3/5a and 3/5b 3.27)

> Single Axle A_f = 1.54 Allowable Axle = 12.5 tonnes a)

> Allowable Axle = 6.0 tonnes 2 Axle bogie A_f = 0.75 b)

From Table 3/6 Max Gross Vehcle Weight = 18 tonnes

187 17/10/or

Sensitivity Analysis Condition Factor Reduced to 0.4

Project:

80714

Structure:

Southill Road Railway Bridge HIB27

Sheet No.

2

MEXE Analysis to BA 16/97 (With axle lift-off)

L = 8.522

 $r_c = 1.951$ $r_a = 1.54$ d = 0.48

h+d = 0.691

Adjustment to limit h+d to 2*d not required 1

 $F_{b} = 1$

 $F_f = 0.7$

 $F_{w} = 0.9$

 $F_{mo} = 1$ $F_{d} = 0.9$ $F_{CM} = 0.4$

Clause No:

Provisional Axle Load = $740(d+h)^2/L^{1.3}$ = 21.80 tonnes 3.10)

Span/Rise Factor $L/r_c = 4.37$ 3.11)

Hence $F_{sr} = 0.94$ (Fig 3/3)

3.12)

Profile Factor $F_p = 2.3((r_c - r_q)/r_c)^{0.6} =$

3.13)

Material Factor $F_m = ((F_b * d)+(F_f * h)) / (d+h) =$

3.16)

Joint Factor $F_j = F_w * F_d * F_{mo} = 0.81$

3.24)

Modified Axle Load = $F_{sr} * F_p * F_m * F_j * F_{CM} * PAL =$

tonnes 5.47

3.27)

With axle lift - off: Fig's 3/5a and 3/5b

Af for 2 axle bogie = 0.75

a)

Single Axle A_f = 1.54 Allowable Axle =

8.0 tonnes

b)

2 Axle bogie A_f = 0.75 Allowable Axle =

4.0

tonnes

From Table 3/6 Max Gross Vehcle Weight = 10 tonnes

APPENDIX D

Assessment Inspection Report

British Rail Property Board, 2001/02 Client: Bedfordshire County Council

Southill Road Railway Bridge

No. HIB27

Draft Assessment Inspection Report

080714 March 2002

DOCUMENT ISSUE RECORD

Document	Status	Issued to	No. of copies	Date of issue	Signed
					

Contents

1.00	Introduction, Location Plans and General Arrangement	Page 2
2.00	Inspection and Inspection Report Form BE11/94	Page 6
3.00	Conclusions	Page 13
4.00	Recommendations	Page 14

Appendices

Α	Photographs
В	Defects Drawings
С	Statutory Undertakers Apparatus Information
D	Dimension Check List and Survey Drawings
Е	List of Record Drawings
F	Site Factors Affecting Assessment
G	AIP Form


Copyright Babtie Group Limited. All rights reserved.

No part of this report may be copied or reproduced by any means without prior written permission from the Babtie Group Limited. If you have received this report in error, please destroy all copies in your possession or control and notify Babtie Group Limited.

This report has been prepared for the exclusive use of the commissioning party and unless otherwise agreed in writing by Babtie Group Limited, no other party may use, make use of or rely on the contents of the report. If others choose to rely upon this report they do so entirely at their own risk. No liability is accepted by Babtie Group Limited for any use of this report, other than for the purposes for which it was originally prepared and provided.

Opinions and information provided in the report are on the basis of Babtie Group Limited using due skill, care and diligence in the preparation of the same and no explicit warranty is provided as to their accuracy. It should be noted and it is expressly stated that no independent verification of any of the documents or information supplied to Babtie Group Limited has been made.


1.00	Introduction
1.01	Structure Details
	Bridge no. HIB27 OS reference TL 0907 4689 Date of inspection 20/03/2002
1.02	Structure Description
1.02.1	The bridge carries the U147 Southill Road two-way single carriageway over a disused railway and is located 1 km south of Cardington village. The date of construction is not known but bridges on the same line were possibly built in 1855.
1.02.2	The bridge is a single span 4-ring brick arch springing from brick abutments. The wingwalls, spandrels and parapets are of brick.
1.02.3	There are no weight limit signs on the bridge.
1.03	Structure dimensions
	Skew Span: 8.49m Skew: 21° Width between parapets: 6.03m





East Elevation

1.00	Introduction cont.
1.04	Inspection Details
1.04.1	The structure was inspected as part of the British Rail Property Board Assessment programme.
1.04.2	The structure was inspected in accordance with Department of Transport documents:
	Standard BD 63/94 Inspection of Highway Structures. Advice Note BA 63/94 Inspection of Highway Structures.
1.04.3	The structure was inspected on the 20 th March 2002.
1.04.4	The inspection was undertaken during the day. The weather conditions were good/rain.
1.04.5	The inspector was P Butler.
1.04.6	The structure was inspected on foot and using an underbridge unit.
1.04.7	No record drawings are available.
1.04.8	The bridge was surveyed by the Bedford Babtie Group survey team and a plan, elevations and cross sections produced. Copies are enclosed in Appendix D.
1,05	Previous Inspection and Summary
1.05.1	No previous inspection records were made available.

Location Plans







Drawing Number HIB27/05 Notes Do not scale this drawing

<a>Babtie

Client	BEDFORDSHI COUNTY COUNTY			
Project	ASSESSMENT OF BR PROPERTY BOARD ST			-
Title	SOUTHILL ROAD RAILW U147 CARDINGT GENERAL ARRANGE	NOT	IDGE	
Drawing No.	HIB27/05	ТТ		
Scale	AS SHOWN	Date	APRIL	2002
	Dec	_		7777

Copyright reserved

Babfle Group Ltd

Box 272, The Merton Centre, 45 St.Peters Street, Bedford MK40 2ZY

Structure Insp	Structure Inspection Report							BE 11/94	94
Structure Number	HIB27					Grid Reference	erence	TL 0907 4689 E N	
Structure Name	SOUTHILL ROAD RAILWAY BRIDGE	IDGE				Location (Parish)	(Parish)	CARDINGTON	
Date of Inspection	20 MAR 2002		Type of Inspection	Ispection	9		S	Inspected by	
		O)verall As:	Overall Assessment	9	<u>"</u>	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	From Span 1 To Span	
Defect Assessment	nt Estimated Cost		Extent	Severity	Work	Priority	PD	Comments	
1. Foundation					8			NO VISIBLE DEFECTS.	
2. Inverts or Aprons			B	2	z			SOME DEBRIS.	
3. Fenders									
4. Piers or Columns									
5. Abutments			В	2	z			CRACKS. HOLLOW/SPALLED BRICKWORK IVY	\ <u>\</u>
6. Wing walls		 	U	3	<u>~</u>	Σ		CRACKS. BULGING, SPALLED BRICKWORK IVY	<u> </u>
7. Retaining walls or Revetments	evetments								
8. Approach Embankments	ents		В	2	z			SOME SETTI EMENT TO EDGES	
9. Bearings									
10. Main beams/Tunnel portals/Mast	il portals/Mast		<u> </u>						
11. Transverse beams/Catenary Cables	Catenary Cables								
12. Diaphragms or bracings	sbur								
13. Concrete slab									
14. Metal deck plates/Tunnel linings	Tunnel linings								
HIB27 pi.doc									

HIB27 pi.doc

Defect Assessment (Cont.)

15. Jack arches

16. Arch ring/Corrugated Metal

17. Spandrels

18. Tie rods

19. Drainage Systems

20. Waterproofing

21. Surfacing

22. Service Ducts

23. Expansion Joints

24. Parapets/Handrails

25. Access gantries or walkways

32. Dry Stone Walls

33. Troughing

Priority Work Severity Extent Estimated cost

8

O	4	ھ	I	CRACKS. HOLLOW BRICKWORK. POOR JOINTS.
Q	3	Œ	I	CRACKS. BULGING. MOVEMENT.
		В		MINOR SEEPAGE/DAMP AREAS.
		A		SEEPAGE.
В	2	Z		MINOR SETTLEMENT. CRACK.
D	3	В	н	SPALLING. POOR JOINTS. VEGETATION.

Reason for priority allocation

ARCH RING

SPANDRELS

WATERPROOFING **PARAPETS**

Consider installing waterproofing to prevent water ingress.

Remove roots/repoint joints in intrados and replace brickwork in arch ends to prevent further deterioration. Install RC backing to spandrels to prevent further movement.

Remove vegetation, replace spalled/hollow brickwork and repoint to prevent further deterioration.

Replace spalled brickwork and repoint to prevent further deterioration and restore strength.

Signed Name Date

2.00	Inspection
2.01	Foundations
2.01.1	There are no record drawings available. The foundations are assumed to be spread footings.
2.01.2	There would not appear to be any foundation defects.
2.02	Invert
2.02.1	There are no record drawings available. From inspection the invert is of soil (see plates 1 and 2).
2.02.2	The invert has some debris present, including the missing copings from the parapet, and there is evidence of fires adjacent to the abutments (see plates 1-5).
2.05	Abutments
2.05.1	There are no record drawings available. From inspection the abutments are of brick (see plates 1-5).
2.05.2	The south abutment has a vertical hairline crack 0.85m from the east end for much of the height. There is a diagonal hairline crack from the stringcourse 0.6m from the east end running down to the abutment end at half height then horizontally into the east face and pilaster 1-2mm wide. There is a large area of hollow sounding brickwork west of centre, which may be fire damage. There is some spalled and hollow sounding brickwork to the east end base. The west face has a horizontal crack 1mm at the base plinth and a horizontal hairline crack at the springing, both extending into the pilaster. The pilaster has a further horizontal crack 1-2mm wide towards the top (see plates 3 and 4).
2.05.3	The north abutment has a vertical hairline crack west of centre for the full height extending into the arch. There is a vertical crack towards the west end at half height which extends horizontally to the west end just above the base plinth at 1mm wide. The west end has some ivy growth. The east end has two vertical hairline cracks over the centre, one running horizontally at half height into the east face and pilaster, joining a vertical hairline crack. The east end brickwork is spalled and hollow sounding and has seepage deposits. The east face has a horizontal crack 1-2mm wide at springing level running through the pilaster and vertically up the wingwall joint. The west pilaster is overgrown with ivy (see plates 5 and 6).

_	2.00	Inspection
-	_,,,	
•	2.06	Wingwalls
-	2.06.1	There are no record drawings available. From inspection the wingwalls are of brick (see plates 7-9)
-	2.06.2	The southeast wingwall/pilaster joint is cracked at the top 1mm wide. The top of the wall has much ivy growth. The centre has an area of surface spalling and hollow sounding brickwork, some spalling up to 100mm deep and a slight bulge. The base adjacent to the abutment has spalling up to 100mm deep (see plate 7)
-	2.06.3	The southwest wingwall has a diagonal hairline crack emanating from the abutment joint at springing level running down towards the base. There is a horizontal crack at half height 2mm wide from the centre to the copings. The central area is bulging and hollow sounding (see plate 8).
	2.06.4	The northwest wingwall is covered in ivy (see plate 9).
-	2.06.5	The northeast wingwall has a spalled area adjacent to the abutment just above half height. There are some surface spalled bricks and poor joints present.
•	2.08	Approach Embankments
-	2.08.1	There are no record drawings available. From inspection the bridge has approach embankments to both sides (see plates 1, 2 and 10).
•	2.08.2	The embankments are heavily overgrown in places with numerous trees growing, some adjacent to the bridge (see plates 1, 2 and 10).
-		
-		

2.00	Inspection
2.16	Arch Ring
2.16.1	There are no record drawings available. From inspection the arch is of 4-ring brick construction 460mm thick (see plates 1, 2 and 11).
2.16.2	The arch west face original brickwork over the crown between the blue brick facing is all hollow sounding, cracked, spalled and loose. The face north of the crown is bulging 10mm. There is a crack around the barrel running from the south abutment at hairline wide, over the south ¼ point at 5mm wide, over the crown at hairline wide, over the north ¼ point at 3-4mm wide and finishing near the north abutment at hairline wide (see plates 11-16).
2.16.3	The arch intrados has a longitudinal crack 200mm from the west face, hairline at the north abutment, 3-4mm at the north ¼ point, 10mm at the south ¼ point and hairline at the south abutment. There is a crack running parallel 400mm from the face hairline at the crown, 2-3mm over the north ¼ point then running diagonally to the north abutment at hairline wide and a short crack 400mm from the face 1-2mm wide towards the south abutment. The west end over the crown has spalled bricks and the brickwork to the south side is hollow sounding. The northwest corner of the intrados has ivy roots in the joints. The west end has seepage deposits to both sides. There is a longitudinal crack at the centre 2-3mm wide running from the north abutment to south of the crown and a longitudinal hairline/0.5mm wide crack 0.6m west of centre from near the north abutment to near the crown. There is an area of eroded joints 20mm deep at the centre towards the north abutment. There is a longitudinal crack 240mm from the east face, hairline wide at the north abutment, 2-3mm at the north ¼ point, 3-4mm at the crown, 2-3mm at the south ¼ point then 440mm from the face running to the south abutment 2-3mm wide. The east end has seepage deposits to both sides and there is an area of spalled and hollow sounding brickwork at the south abutment (see plates 12, 14, 16-18, 20, 22 and 26).
2.16.4	The arch east face has a crack around the barrel running from the north abutment to the north ¼ point 1mm wide and from the south abutment to the south ¼ point 1mm wide. There is some bulging with the spandrel wall over the south ¼ point (see plates 19-26).

2.00	Inspection
2.17	Spandrels
2.17.1	There are no record drawings available. From inspection the spandrels are of brick (see plates 1 and 2).
2.17.2	The west spandrel/arch barrel joint is cracked from the south abutment at hairline wide over the south ¼ point at 5mm wide, over the crown at hairline wide and at the north ¼ point 3-4mm wide, extending towards the north abutment at hairline wide. At the north ¼ point there is a horizontal crack 1-2mm wide running from the arch barrel/spandre joint to the pilaster. The south side has a vertical crack south of the ¼ point from the arch barrel at hairline wide to the parapet stringcourse 2-3mm wide. There is a vertical hairline crack at the south pilaster joint from the parapet stringcourse to half height and continuing horizontally into the pilaster. The north end of the spandrel has ivy growth (see plates 12-15).
2.17.3	The east spandrel has a crack around the barrel running from the north abutment to the north ¼ point 1mm wide. The barrel/spandrel joint is cracked from the south abutment to the south ¼ point 1mm wide then vertically up through the spandrel. The south side has a horizontal crack 1mm wide at half height and a vertical crack 4-5mm wide at the south end. The south side is bulging. The north side has some bulging and an area of eroded joints 20mm deep (see plates 19-26).
2.19	Drainage Systems
2.19.1	There are no record drawings available. From inspection there are no drainage weep-pipes visible.
2.19.2	The abutments have some minor seepage deposits and the wingwalls have some damp patches along the base.
2.20	Waterproofing
2.20.1	There are no record drawings available. The waterproofing could not be inspected.
2.20.2	The arch has seepage deposits at both ends (see plates 17 and 18).

2.00	Inspection
2.21	Surfacing
2.21.1	There are no record drawings available. From inspection the surfacing is 4.65m wide and there are soft verges to both sides (see plates 27 and 28).
2.21.2	The carriageway has a wide trench reinstatement over the east side. There is minor cracking across the west side of the carriageway at the south end. The west carriageway edge has slight settlement up to 10mm at both ends of the parapet (see plates 27 and 28).
2.24	Parapets
2.24.1	There are no record drawings available. From inspection the parapets are of brick (see plates 1, 2, 27 and 28).
2.24.2	The west parapet has some spalled bricks and poor joints and has ivy growth to the ends. The north pilaster brickwork has cracking and is dislodged 20mm (see plates 2, 13 and 27-29
2.24.3	The east parapet has much spalling and poor joints, with much ivy growth in the joints. The north pilaster has a vertical crack 1mm wide and there are missing copings adjacent to the wall. The south end has some bulging with the spandrel wall below and there is vegetation growth at the south pilaster. There is a diagonal crack 1mm wide to the road face adjacent to the south pilaster (see plates 1, 19-21, 25, 27, 28 and 30).

3.00	Conclusions
3.01	The bridge is in poor condition and has spandrel movement and longitudinal cracks at the arch ends.
3.02	The spalled brickwork and poor joints in the abutments would appear to be due to weathering and ivy growth, which is made worse by the seepage present. The hollow sounding brickwork may be due to fire damage, as the walls have evidence of fires adjacent. The defects do not appear severe at present. The vertical crack at the north abutment centre may indicate there is some movement to the abutment, but this would not appear excessive. The cracking at the abutment ends may be due to some movement to the abutment and wingwalls and possibly the movement of the spandrels and arch ends.
3.03	The spalled brickwork and poor joints in the wingwalls would appear to be due to weathering and ivy growth, which should be repaired to prevent further deterioration.
3.04	The approach embankments are overgrown but this would not appear to be causing distress to the structure.
3.05	The arch intrados longitudinal cracking at the arch ends indicates both spandrels are moving, taking the arch ends with them. The longitudinal cracking at the centre may indicate there is some movement to the arch and north abutment.
3.06	The cracking and bulging to the east spandrel indicates movement has taken place. The longitudinal cracking at the arch ends indicates both spandrels are moving, taking the arch ends with them. The spandrels require strengthening, possibly with reinforced concrete backing, to prevent further movement and damage to the structure.
3.07	The seepage in the arch indicates the waterproofing is ineffective. The water ingress may be causing the spalling and poor joints present. Waterproofing should be considered to prevent the water ingress.
3.08	The surfacing defects are minor only and do not require repair at the present time.
3.09	The east parapet has many open joints and spalled bricks, which would appear to have been caused by the growth of ivy along the wall, there still being many roots in the joints. The wall requires repointing, and the spalled and missing brickwork and copings replacing, to restore the parapet strength. The dislodged brickwork to the west parapet end appears to be due to vehicle impact. The wall requires the dislodged section rebuilding and the ivy growth removing and joints repointed.

4.00	Recommendations
4.06	Wingwalls
4.06.	Remove vegetation, replace spalled/hollow brickwork and repoint to prevent further deterioration.
4.16	Arch Ring
4.16.1	Remove ivy roots from the west end of the arch intrados and repoint joints to prevent further deterioration.
4.16.2	Replace brickwork to arch faces to prevent further deterioration.
4.17	Spandrels
4.17.1	Install RC backing to spandrels to prevent further movement.
4.20	Waterproofing
4.20.1	Consider installing waterproofing to prevent water ingress.
4.24	Parapets
. 4.24.1	Remove ivy roots from the parapet brickwork, repoint joints, and replace spalled and displaced/missing bricks and copings to prevent further deterioration and restore parapet strength.



Appendix A

Photographs

Plate 1	East elevation.
Plate 2	West elevation.
Plate 3	South abutment.
Plate 4	South abutment west end.
Plate 5	North abutment.
Plate 6	North abutment east end.
Plate 7	Southeast wingwall.
Plate 8	Southwest wingwall.
Plate 9	Northwest wingwall.
Plate 10	South approach embankment.
Plate 11	Elevation through arch from the west side.
Plate 12	Arch and north abutment west end.
Plate 13	Arch west face north side.
Plate 14	Arch west end over north abutment.
Plate 15	Arch west face and spandrel south side.
Plate 16	Arch west end over south abutment.
Plate 17	Arch north side.
Plate 18	Arch south side.
Plate 19	Elevation through arch from the east side.
Plate 20	Arch east face and spandrel south side.
Plate 21	Arch east face, spandrel and parapet south side.
Plate 22	Arch and south abutment east end.
Plate 23	Arch east face and spandrel south side.
Plate 24	East spandrel south end.
Plate 25	Arch east face and spandrel north side.
Plate 26	Arch and north abutment east end.
Plate 27	Carriageway elevation from the south.
Plate 28	Carriageway elevation from the north.
Plate 29	West parapet north end.
Plate 30	East parapet north end.



Plate 1 East elevation






Plate 2 West elevation



Plate 3
South abutment










Plate 5 North abutment








Plate 7 Southeast wingwall




Plate 8
Southwest wingwall




Plate 9 Northwest wingwall




Plate 10 South approach embankment




Plate 11
Elevation through arch from the west side




Plate 12
Arch and north abutment west end






Plate 13 Arch west face north side










Plate 15
Arch west face and spandrel south side








Plate 17 Arch north side






Plate 18 Arch south side



Plate 19
Elevation through arch from the east side









Plate 21
Arch east face, spandrel and parapet south side









Plate 23 Arch east face and spandrel south side

Plate 24 East spandrel south end







Plate 25 Arch east face and spandrel north side.

Plate 26 Arch and north abutment east end






Plate 27 Carriageway elevation from the south




Plate 28 Carriageway elevation from the north




Plate 29 West parapet north end




Plate 30
East parapet north end

Appendix B

Defects Drawings

Drawing Number

Title

HIB27/6

Elevations Defects

HIB27/7


Arch Defects

HIB27/8


Abutment Defects

HIB27/9


Carriageway Defects





EAST ELEVATION




WEST ELEVATION









NORTH ABUTMENT





Babtie

Client		BEDFORDSHIRE COUNTY COUNCIL								
Project		ASSESSMENT OF BRITISH RAIL PROPERTY BOARD STRUCTURES								
Title	SOUTI	HILL ROAD RAILV U147 CARDING ABUTMENT DEF	TON							
Drawing No.	HIB27/08									
Scale	1:100		Date APRIL 2002							
	Drawn SR	Checked PDB	Approved A							
Copyright reser Babtie Group L Box 272, The	.td	St.Peters Street, Be	edford MK40 2ZY							



No. HIB27

_	Southill Road Railway Bridge No. H
-	Appendix C
}~~	Statutory Undertakers Apparatus Information
-	There is no information regarding Statutory Undertakers Apparatus.
-	
-	
-	
-	
-	
gane	
-	

Appendix D

Survey Drawings

Sheet 1

Structure Dimensions

Drawing Number

Title

HIB27/1

Plan and Levels

HIB27/2

East Elevation

HIB27/3

West Elevation

HIB27/4


Cross section 1


Appendix D

Sheet 1

Structure Dimensions

Structural Element	Surveyed Dimension
Skew Span	8.49
Skew	21°
Ring Thickness	0.46
Width between parapets	6.03
Carriageway width	Varies - approx. 4.65
West verge	Varies - approx. 0.73
East verge	Varies - approx. 0.65
Parapet Width	0.34





DATI	JM=26.	000
DHI	יס ב–ויור	UUU

	 '' '	Ţ					1		-		1						- 11	
CHAINAGE	5, 000	6, 000	7, 000	8, 000	000	000 %	10, 000	11, 000	12, 000		13, 000	14,000	15, 000		16, 000	17, 000	18, 000	
GROUND	31, 728 31, 909 32, 021		26. 821 26. 775 - 26. 714 -			26. 701		26, 642				26. 635		26. 729	26, 887 - 27, 058 -		32, 060 - 31, 765 =	
ARCH			29, 764	30, 269	30, 947	31. 227	31. 541	31 719	31, 705	31, 618 -	31, 510	31. 289	30, 996 30, 832 30, 655	30, 112 -			N.	
EDGE OF CARRIAGEWAY	32, 020		32, 210			32, 328			32, 392			32 421	<u>.</u>			32, 320		32, 224 - 32, 188
PARAPET	33, 708 -	33, 779	33, 698 -		33, 730 -	33, 741		33, 749 -			101	33, 725		33, 682		33, 752	33, 681	

Drawing Number

HIB27/2

Notes

All levels are related to the OSBM on Southill Road Railway Bridge Value 33,710m

2.
Direction of elevation is perpendicular to the face of the structure

Do not scale this drawing


ev	Date		Check	bes
0 1100	T T	didming		

<a>Babtie

Client	BEDFORDSHIRE COUNTY COUNCIL
Project	ASSESSMENT OF BRITISH RAIL PROPERTY BOARD STRUCTURES
Title	SOUTHILL ROAD RAILWAY BRIDGE U147 CARDINGTON EAST ELEVATION

Drawing No.	HIB27/2			
Scale	HS=1:100 VS=	1:100	Date	FEB 2002
	Drawn DMS	Checked /	Appro	ved .
		OR OF		

Copyright reserved Babtle Group Ltd 95 Bothwell Street, Glasgow G2 7HX



33, 757

CHAINAGE

GROUND

PARAPET

33, 718

33, 627

ARCH

Drawing Number HIB27/3 All levels are related to the DSBM on Southill Road Railway Bridge Value 33, 710m Direction of elevation is perpendicular to the face of the structure Do not scale this drawing

<a>Babtie

Client	1	BEDFORDSHIRE COUNTY COUNCIL								
Project		ASSESSMENT OF BRITISH RAIL PROPERTY BOARD STRUCTURES								
Title	U	SOUTHILL ROAD RAILWAY BRIDGE U147 CARDINGTON WEST ELEVATION								
Drawing No.	HIB27/3									
Scale	HS=1:100 VS=1:1	00 1/1	Date	FEB 2	002					
	Drawn DMS Checked Approved									
Copyright reserved Babtle Group Ltd 95 Bothwell Street, Glasgow G2 7HX										



DATUM=31, 000

CHAINAGE	-3, 612	-3, 282	-2. 741	-2, 492	0000	2,511	2, 817	3, 184	3, 519
SECTION 1	33, 756 =	32, 615	32, 468	32, 398	32.406	32, 394	32, 493	32, 499	33, 743 32, 479
SOFFIT	31, 683								31, 711

Drawing Number HIB27/4 All levels are related to the DSBM on Southill Road Railway Bridge Value 33, 710m Do not scale this drawing <a>Babtie

Client	-	BEDFORDSHIRE COUNTY COUNCIL								
Project		ASSESSMENT OF BRITISH RAIL PROPERTY BOARD STRUCTURES								
Title	U	SOUTHILL ROAD RAILWAY BRIDGE U147 CARDINGTON CROSS SECTION 1								
Drawing No.	HIB27/4									
Scale	HS=1:50 VS=1:50	A	Date	FE	3 2003					
	Drawn DMS Checked Approved .									
Copyright reser	ved .td 95 Bothwell Street	:. Glasgow G2 7HX	(

Appendix E

List of Record Drawings

None

Appendix F

Site Factors Affecting Assessment

Arch Profiles and Assessment Data

Sheet 1 Parameters for Assessment

Sheet 2 Carriageway Profile and Statutory Undertakers Plant

Appendix F

Sheet 1 Parameters for Assessment

	Arch Barrel Material and Condition					
Arch Barrel Material						
Brick 4-ring (460mm). Not engineering bricks but appear of good quality.						
	Arch Barrel Material Condition					
(Good condition generally but has some spalled bricks.					
	Arch Barrel General Condition					
	centre. Large longitudinal cracks at both ends. Intrados brickwork in sound on apart from ends and arch appears to have a good shape.					
	Fill Material					
	Well compacted. Minor settlement.					
:	Mortar Joints					
	Joint Width					
	Less than 10mm					
	Joint Condition					
Generally good cond	lition but has some patches of eroded joints up to 20mm deep. Some ivy					
	growth to northwest corner.					
	Depth missing 20mm					
	ZOTTITI					
	Factors for assessment					
Barrel Factor F _b	1.0					
Fill Factor F _f	0.7					
Joint Width Factor Fw	0.9					
Mortar Factor F _{mo}	1.0					
Joint Depth Factor F _d	0.9					
Condition Factor F _{cm}	0.6					
}	Arch Profile					
The arch elevation surveys show that the arch appears to have a uniform circular profile.						

Appendix F

Sheet 2 Carriageway Profile and Statutory Undertakers Plant

Affect of Carriageway Profile

Lift-off:

Lift-off will be considered in the assessment, as the carriageway over the

structure is curved.

Centrifugal Effects:

Centrifugal effects are not considered in the assessment. The carriageway over

the structure is nearly straight.

Affect of Statutory Undertakers Apparatus

No information is available on existing services.

Appendix G

AIP Form