


**BRB (Residuary) Ltd
Major Works Programme 2004/2007**



**VAR9-1220 BE4 ASSESSMENT
PROGRAMME**

**ASSESSMENT AND INSPECTION
REPORT**

BENTON ROAD, ILFORD

BRIDGE REF: NPB 719



February 2005

Document control sheet
Form IP180/B

Client: BRB (Residuary) Ltd
 Project: Major Works Programme 2004/2007
 Title: VAR 9 –1220 BE4 Assessment
 Programme

Job No: J24110GA –NPB719

	Prepared by	Reviewed by	Approved by
ORIGINAL	NAME [REDACTED]	NAME [REDACTED]	NAME [REDACTED]
DATE 19 Jan 2005	SIGNATURE	SIGNATURE	SIGNATURE

REVISION Final Report	NAME [REDACTED]	NAME [REDACTED]	NAME [REDACTED]
DATE 16 Feb. 05	SIGNATURE [REDACTED]	SIGNATURE [REDACTED]	SIGNATURE [REDACTED]

REVISION	NAME	NAME	NAME
DATE	SIGNATURE	SIGNATURE	SIGNATURE

REVISION	NAME	NAME	NAME
DATE	SIGNATURE	SIGNATURE	SIGNATURE

This report, and information or advice which it contains, is provided by JacobsGIBB Ltd solely for internal use and reliance by its Client in performance of JacobsGIBB Ltd's duties and liabilities under its contract with the Client. Any advice, opinions, or recommendations within this report should be read and relied upon only in the context of the report as a whole. The advice and opinions in this report are based upon the information made available to JacobsGIBB Ltd at the date of this report and on current UK standards, codes, technology and construction practices as at the date of this report. Following final delivery of this report to the Client, JacobsGIBB Ltd will have no further obligations or duty to advise the Client on any matters, including development affecting the information or advice provided in this report. This report has been prepared by JacobsGIBB Ltd in their professional capacity as Consulting Engineers. The contents of the report do not, in any way, purport to include any manner of legal advice or opinion. This report is prepared in accordance with the terms and conditions of JacobsGIBB Ltd's contract with the Client. Regard should be had to those terms and conditions when considering and/or placing any reliance on this report. Should the Client wish to release this report to a Third Party for that party's reliance, JacobsGIBB Ltd may, at its discretion, agree to such release provided that:

- JacobsGIBB Ltd's written agreement is obtained prior to such release, and
- By release of the report to the Third Party, that Third Party does not acquire any rights, contractual or otherwise, whatsoever against JacobsGIBB Ltd, and JacobsGIBB Ltd accordingly assume no duties, liabilities or obligations to that Third Party, and
- JacobsGIBB Ltd accepts no responsibility for any loss or damage incurred by the Client or for any conflict of JacobsGIBB Ltd's interests arising out of the Client's release of this report to the Third Party.

Contents

1	Introduction	1-1
1.1	Remit	1-1
2	General Description and Structural Details	2-1
2.1	Location	2-1
2.2	Construction type	2-1
2.3	Assessment summary	2-1
2.3.1	BE4 Assessment	2-1
3	Existing Information Search	3-1
3.1	Service Search	3-1
3.2	SI Results	3-1
3.3	Existing Drawings	3-1
4	Structure Condition	4-1
4.1	General	4-1
4.2	Main Superstructure	4-1
4.2.1	External Girders	4-1
4.2.2	Internal Girders	4-2
4.2.3	Tie rods	4-2
4.2.4	Jack Arches	4-3
4.2.5	Bearings	4-3
4.3	Abutments	4-4
4.4	Wingwalls	4-4
4.5	Parapets	4-4
4.6	Road Surface	4-4
4.7	Formation	4-4
5	Summary Condition	5-1
6	Assessment to BE4 1967	6-1
6.1	Structural Parts checked to BE4	6-1
6.2	Methodology	6-1
6.3	Results	6-1

7 Recommendations

7-1

Table 5-A Effective area of flanges as % of original area (Combined figures for both plates)

5-1

Appendix A - Photographs
Appendix B - Services Search
Appendix C - Trial Pit and Metal Test Results
Appendix D - Form AA
Appendix E - Form BA
Appendix F - Calculations

1.1 Remit

Jacobs was appointed by BRB(R) to conduct the site survey at NPB/719 in sufficient detail to provide data for BE4 assessment work or information for remedial works contracts.

Structural Soils Ltd excavated an inspection pit on the bridge deck to determine typical deck construction and to examine the top flange of one of the internal girders.

2.1 Location

Bridge NPB 719 carries Benton Road, Ilford, a class "C" urban distribution road over the track bed of the former Newbury Park Branch at track mileage 8m 38ch (Photograph No.1). The carriageway is 8.17m wide with paved footways about 2.05m wide on both sides (Photograph No.2). The road is subject to a 30 mph speed limit.

The OS grid reference is TQ 448 874. The bridge is located within the London Borough of Redbridge.

2.2 Construction type

The structure comprises nine spanning wrought iron riveted plate girders with brick jack arch construction between the girders. All girders have the same construction, with 27" web depth, 14" flange width and $3\frac{1}{2} \times 3\frac{1}{2} \times \frac{1}{2}$ " angles. The central section of the girders has two $\frac{1}{2}$ " flange plates top and bottom reducing to one plate at 2'-6" from the support. The deck is square to the abutments with clear span measured at 25'-3" (7.71m). Girder spacing is 62" (1580mm). (Figures 1 and 2: Appendix F.)

The brick jack arches are covered with concrete to the level of the girder top flanges. Infill above the concrete under the footway consists of gravelly sand and medium sand.

The abutments and wingwalls are brick construction. The girders span onto sandstone bearing blocks, which are built in to the brick abutments. There appears to be a metal bearing plate between the bearing block and the girder bottom flange.

The parapets are brick. There are end pilasters capped with stone copings.

Date of construction is stated as 1903.

2.3 Assessment summary

2.3.1 BE4 Assessment

The bridge is calculated to have full C&U capacity, according to the BE4 assessment code.

3 Existing Information Search

3.1 Service Search

Documentation to be obtained from Structural Soils Ltd

3.2 SI Results

A trial pit was undertaken as part of the survey. This was located in the north footway at approximately mid-span and exposed the top flange of the first internal girder. Data on the trial pit is included in appendix C. (Photograph No.8).

A metal sample was taken from the south edge girder.

3.3 Existing Drawings

No drawings have been found for the bridge. Limited dimensional and construction information was available from old assessments.

4.1 General

The inspection for BE4 assessment was undertaken on Wednesday 12 January 2005. Weather on the day of inspection was dry and sunny with temperature being about 8°C.

The bridge is partially infilled. Access was possible via a gap in the fence on the south side of the road. There is approximately 1.4m headroom under the girders. There has been extensive fly tipping under the bridge.

For the purposes of recording inspection data the girders are numbered from south to north, No.1 being the south edge girder. The jack arches are referred to as 1/2 etc. this being the jack arch between girder 1 and girder 2.

4.2 Main Superstructure

4.2.1 External Girders

Girder No. 1 (South edge girder)

The face of the girder is in fair condition, with only slight breakdown of the paint system. (Photograph No. 3)

The bottom flange displays slight laminar expansive over most of its length, but between 2 and 3.5m from the west abutment there is more extensive corrosion of the bottom flange plates. In this zone, the lower plate can only be considered effective over the centre part of the flange between the lines of the rivets owing to extensive corrosion and the upper plate also displays some section loss. It is estimated that approximately 30% of the bottom plate remains effective and 80% of the upper plate.

The exposed edge of the top flange also displays extensive expansive corrosion. At mid-span it appears to have expanded by up to 50mm and this may have lifted the parapet wall causing a vertical fracture. An attempt to control this corrosion appears to have been made by plastering the laminating edge of the flanges with an epoxy sealant.

Girder No.9 (North edge girder)

There is extensive laminar corrosion of both the bottom and top flanges throughout their length, having expanded to two or three times their original thickness. The expansion appears to have caused a crack in the parapet similar to that in the south parapet. At about 2.5m from the west abutment there is an exceptional bulge of corrosion in the outer leg of the bottom flange. In general, the outer section of the top flange beyond the rivet line must be considered as ineffective. The lower plate of the bottom flange is considered only 30% effective and the upper plate 70%. (Photograph 4)

The web displays considerable loss of the paint system and surface corrosion.

4.2.2 Internal Girders

Girder No.2

There is severe laminar corrosion of the bottom flange of the girder from the east end of the second plate to mid-span (Photograph 5). The upper plate is estimated to be only 60% effective and the lower plate 30%.

Girder No.3

The bottom flange of the girder is in fair condition. Maximum corrosion occurs in a zone 1m long, 2.5m from the west abutment. The two flange plates are estimated to be 90% effective.

Girder No.4

In fair condition apart from a zone from the west abutment to quarter span west, where there is moisture emanating from the adjacent jack arch causing active corrosion. The upper plate is taken as 95% effective and the lower plate 70%. Elsewhere the bottom flange is estimated to be 90% effective.

Girder No.5

In a 2m section, 2.5m from the west abutment, there is deep corrosion resulting from active moisture ingress. Most of the rivet heads have been lost in this zone. The lower plate is assumed to be only 50% effective. Elsewhere 90% effectiveness is estimated.

Girder No.6

In fair condition, estimated to be 95% effective apart from a 0.5m long section 2.5m from the west abutment where there is deep corrosion including loss of the rivet heads. 50% loss of the lower plate is estimated in this zone.

Girder No.7

Similar to girder No.6 but with a longer corrosion zone, 1.5m long centred 2.5m from the west abutment; with 50% loss of the bottom plate and loss of all rivet heads.

Girder No.8

This is similar to girder No. 7, but has an additional corrosion zone 2.5m from the east abutment. The top flange of Girder No.8 was exposed by the trial hole. This flange appeared to be in near perfect condition.

4.2.3 Tie rods

Only two tie straps remain on the entire bridge. These appear to have been 2½" by ¼" flats riveted to the underside of the bottom flange of the girder and these remaining ones are highly corroded. The tails of the other straps are still visible at their girder connections. There is evidence that both the edge girders have moved outwards by 5 – 10mm, through repaired damage to the south east cheek wall (Photograph No.7) and cracks at the ends of the outer jack arches.

4.2.4 Jack Arches

(a) Outer Bays

Jack Arch 1/2

The arch is generally in fair condition. There is mortar loss to about 25mm depth throughout and spalling brickwork up to 10mm deep in a patch 1 – 2m from the east abutment. The semicircular infill wall at the east end has a vertical crack 5 to 10mm wide and there are some wide joints in the crown of the arch. This may indicate spreading of the arch as a consequence of lack of tie restraints. There is one tie still in position in this jack-arch located at the east third point.

Jack Arch 8/9

The arch displays extensive mortar loss with open joints 25mm deep. There are signs of slight water ingress at the east end. The semi-circular infill walls, at both ends, display vertical, 5-10mm wide cracks, indicating spreading of the arch.

(b) Inner Bays

Jack arch 2/3

The arch is in fair to good condition with only slight mortar loss.

Jack arch 3/4

The arch is in generally fair condition with slight mortar loss. There is a wet patch close to the west abutment, where water is dripping and mortar loss in this area is 25mm or more.

Jack arch 4/5

There is a wet patch adjacent to girder No.4 about 2m from the west abutment. There are calcareous deposits and open joints 25mm deep in this region. Otherwise it is in fair condition with slight mortar loss.

Jack arch 5/6

Good condition. No significant defects.

Jack arch 6/7

Good condition generally. Small areas with open joints near the abutments. There is one tie-strap remaining in this arch.

Jack arch 7/8

Generally in good condition. There is some moisture ingress at the crown of the arch at the east end resulting in open joints.

4.2.5 Bearings

There appear to be metal bearing plates between the bearing blocks and the bottom flanges of the girders. Only the front edge can be seen. This appears to be lightly corroded, but there is no expansive corrosion as seen on the girder flanges.

4.3 Abutments

The abutment walls are in good condition. There is no sign of settlement or cracking.

4.4 Wingwalls

Wingwalls splay at 45° from the corners of the abutments. At the north side they have been totally infilled. On the south side they are infilled to within 1.5m of the top. The exposed surfaces appear to be in satisfactory condition. There are occasional missing bricks on the SW newel post.

4.5 Parapets

There is a substantial solid brick parapet on both sides of the bridge supported on the edge girders. On both parapets, at approximately one third-span, there are near vertical cracks emanating from the top of the girder and continuing through to the copings. The cracks are wider at the top than the bottom; typically 10mm wide at the top (Photograph No. 6). The pattern of the crack suggests the wall is being lifted upwards at the middle of the span. This could be attributable to the expansive corrosion of the top flange of the supporting beam.

4.6 Road Surface

The road surface is in good condition. There are signs that there may have been settlement behind the abutments which has been infilled. The road in these areas has been recently resurfaced with red asphalt with an imitation brick pattern. It is uncertain whether this was done purely to achieve the decorative effect, or was prompted by repairs to surface defects.

4.7 Formation

The bridge has been infilled to within 1.4m of the girder soffit level with soil fill. There has been extensive fly-tipping under the bridge.

The metalwork of the main girders is in poor condition and this will need to be taken into account in the assessment. The expansive laminar corrosion of the top flanges of the edge girders may have already caused damage to the parapet walls.

The top flanges of the internal girders appear to be in very good condition. It is assumed that the webs of the internal girders, which are embedded in concrete, will also be close to their original condition.

Based on estimation of flange plate loss, the following percentages represent effective flange plate size for use in the assessment:

	Mid-span Top flange	Mid-span Bottom flange	Third span Top flange	Third span Bottom flange
South edge girder 1	50%	55%	50%	50%
Internal girder 2	100%	45%	100%	45%
Internal girder 3	100%	90%	100%	80%
Internal girder 4	100%	90%	100%	80%
Internal girder 5	100%	90%	100%	70%
Internal girder 6	100%	95%	100%	70%
Internal girder 7	100%	95%	100%	70%
Internal girder 8	100%	95%	100%	70%
North edge girder 9	50%	50%	50%	50%

Table 5-A *Effective area of flanges as % of original area (Combined figures for both plates)*

The jack arches are in reasonably good condition and are probably kept intact by the backing concrete. The absence of tie bars (or tie straps in this case) will result in a failure in the empirical assessment method. There is evidence that there has been some outward movement of the edge girders.

The exposed up parts of the abutments are in good condition. Qualitative assessment concludes that they are adequate for the imposed loads.

6.1 Structural Parts checked to BE4

The internal and external girders and the jack arch were assessed according to BE4-1967 and BS 153: Parts 3B & 4: 1958.

6.2 Methodology

The internal and external girders were assessed according to the quick assessment method as outlined in BE4-1967 (clause 303 c).

The external girders were checked under dead load only as there is a girder between the edge girders and the carriageway. Compression buckling of the top flange of the edge girders was considered based on the girders being partially restrained against lateral bending. The internal girders were considered fully restrained by the concrete infill.

The jack arches were assessed based upon the empirical method described in Bridgeguard 3 Current Information Sheet No 22 (Pro-forma for the empirical assessment of brick, masonry and concrete jack arches and associated ties.)

6.3 Results

Following the assessment of the internal and external girders, the girders are found to have full C&U capacity and the use of the bridge should be unrestricted to all the vehicles complying with the Construction and Use Regulations (1967). However, the missing ties from the external jack arches results in their failure because of insufficient lateral restraint. (See Appendix F)

Summary of calculations

Element: Internal Girder (No5)

Action	Location	Dead load effect	Full C&U load effect	Total load effect	Assessed resistance	Live load capacity
Bending	Mid-span	101.4 ton.ft	72.6 ton.ft	174.0 ton.ft	330.0 ton.ft	24 tons C&U
Bending	1/3 span	90.4 ton.ft	72.6 ton.ft	163.0 ton.ft	227.2 ton.ft	24 tons C&U
Shear	Support	15.8 ton	11.6 ton.ft	27.4 ton	40.8 ton	24 tons C&U

Element: Edge girder

Action	Location	Dead load effect	Full C&U load effect	Total load effect	Assessed resistance	Live load capacity
Bending	Mid-span	94 ton.ft	0 ton.ft	94 ton.ft	99.2 ton.ft	Pass
Bending	1/3 span	<94 ton.ft	0	<94 ton.ft	99.2 ton.ft	Pass
Shear	Support	14.6 ton	0	14.6 ton	40.8 ton	Pass

Element: 1st Internal Girder (South)

Action	Location	Dead load effect	Full C&U load effect	Total load effect	Assessed resistance	Live load capacity
Bending	Mid-span	103.9 ton.ft	36.3 ton.ft	140.2 ton.ft	225.1 ton.ft	24 tons C&U
Bending	1/3 span	By inspection			225.1 ton.ft	24 tons C&U
Shear	Support	By inspection				24 tons C&U

Element: tie-rods to edge girders

Based on an empirical assessment in accordance with Bridgeguard 3 Information Sheet 22, the external jack arches are failing due to their missing tie bars. The internal jack arches are laterally restrained by the concrete infill and the adjacent jack arches and they pass the empirical assessment.

The bridge does not serve any particular purpose, the track-bed being partly infilled with soil at the north end and with school built on it to the south. The bridge is easily accessible from the road side and may be being used by the homeless and drug addicts as a shelter (based on the fly-tipping material). The fact that the bridge is located in front of a school playground may create a risk for the children. Infilling should be considered, unless there is an objection from the local council.

While the girders supporting the carriageway have adequate reserves of strength, the edge girders are close to their required capacity and any further corrosion could lead to failure.

If the bridge is retained, the extent of the corrosion of the WI girders makes repair work unrealistic. The bottom flanges could be scraped down to their effective metal parts and a high-build paint should be applied to prevent further corrosion. Tie-bars should be installed at the edge jack arches to stop the lateral movement of the edge girders. There is continuous water leakage through the soffit contributing to the active corrosion of the girders, installation of waterproofing is probably not justified considering a 25 year design life.

Minor brickwork repairs and repointing should be undertaken on the outside faces of the parapet walls and stitching of the vertical cracks. The wingwalls are mainly infilled however repairs should be undertaken to their visible parts.

Appendix A - Photographs



1. South elevation of bridge



2. Benton Road over bridge looking west



3. South edge girder



4. North edge girder



5. Laminar expansive corrosion of Girder No.2



6. Crack in south parapet wall



7. SW Pilaster showing repair to side wall believed to have been caused by outward movement of the girder from lack of tie restraint



8. Trial Pit showing top flange of girder No.8

Appendix B - Services Search

**Structural Soils Ltd
The Potteries
Pottery street
Castleford
West Yorks
WF10 1NJ**

Our Ref: NS/COMP LON/2005/198470

Your Ref: 47101

28 January 2005

Dear Mr [REDACTED]

Bridge over Benton Road Seven Kings Redbridge

Thank you for your recent enquiry regarding the above works. Please find enclosed copies of our mains records plans showing the position of our equipment within your indicated area of interest.

If you have asked questions regarding any of the following subjects a copy of your request has been sent to the appropriate department who will contact you in due course. The Plan Provision team is not able to answer these questions and any further contact should be with the department concerned.

London area Wayleaves Tel. 0208 298 8672

Diversions including budgetary estimates Tel. 08701 964599. Fax. 08456 500248.

For network loading KVA etc. Send all details by Fax only to 08456 500248.

New Connections 08456 500247.

General Enquiries, London area 08701 963090

Supply Fault Information (Power cut help line) 08000 280247.

Any work near overhead plant represents a serious risk to life if safe clearances are not maintained. All work should be carried out in accordance with the Electricity at Work Regulations and the Health and Safety Executive guidance document GS6. Work shall not commence on site until we have agreed the necessary safety precautions in writing. GS6 site visits can be arranged via our General Enquiries Line on 08701 963090.

Service cables and Street lighting cables are not always shown on plans for the London area. These cables must be assumed to exist to any nearby property or street lights/road signs in the vicinity. The contractor is held responsible for locating these cables by hand before using any machinery and for any of the damage caused to our network. EDF Energy DO NOT offer an on site cable location service to contractors.

Yours sincerely

[REDACTED]
Networks Service



Plotted On: 28/01/2005
Plotted By: Lynn Thorn
GSS/ERMS REF Scale 1:500

Plot Layer: sssi

Page of 1
unset

SAFETY

The position of the apparatus shown on this drawing is believed to be correct but the original landmarks may have been altered since the apparatus was installed. The exact position of the apparatus should be verified by the use of a suitable cable location device prior to excavation using suitable hand tools. A separate record is kept for each service cable but its route is not necessarily shown on this record. It must be assumed that there is a service cable into each property, lamp column and street sign, etc. All cables must be treated as being live unless proved otherwise by a CEE Energy Supervisor. The information provided must be given to all people working near the London Electricity apparatus.

FREE BOTTLE - SKI PHONE 88701 963797

This plan has been issued for safety purposes in relation to the Electricity Network.
Do not use for excavation purposes more than 3 months after the issue date

PRIMARY CABLES
EXTRA HIGH VOLTAGE CABLES (EHV) 22,000 TO 132,000 Volts

Depth normally 750mm cover in carriageway & 600mm cover in footway.

$S \cdots S \cdots S \cdots S \cdots S \cdots S$
indicates part of route where cover is less than normal.

Before digging within one metre of these cable routes

Telephone 0870: 963797

in order that the Company's apparatus may be located on site and any necessary protection works agreed.

N.B. THRUST BORDERS OR MOLES MUST NOT BE USED WITHIN THE VICINITY OF ANY CABLES BELONGING TO EDF ENERGY WITHOUT FIRST CONTACTING THIS COMPANY.


ADVICE TO CONTRACTORS ON AVOIDING
DANGER FROM BURIED ELECTRICITY
CABLES.

- 1) Do have cable drawings with you on site and check them before you start the excavation.
- 2) Do have a cable locator tool on site and use it to help you.
- 3) Mark out the location of electricity cables.
- 4) Do not use a mechanical excavator within 0.5m of electricity cables.
- 5) Use spades and shovels in preference to other tools.
- 6) Never disturb electricity cables and joints or their protective covers.


REPORTING DAMAGED CABLES
EDF Energy 0800 780078

EDF Energy 0800 780078


These basic safety precautions are explained in detail in the HSE booklet HSG247 – Avoiding Danger from Underground Services, a copy of which may be obtained from your supervisor or H&SO.



Playing Field



Based upon the Ordnance Survey map by EDF Energy Ltd. by permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationary Office. (C) Crown Copyright. (C) EDF Energy Networks (LPN) plc or EDF Energy Networks (SPN) plc each being a distribution licensee under section 61(a) or (b) of the Electricity Act 1989. All rights reserved.



Plot Description: 198470 HW
BENTON ROAD 161

Plotted On: 28/01/2005
Plotted By: Lynn Thorne
GSS/ERMS REF
Scale 1:500

Page of 1
unset
Plot Layer: sssi

STREET

The position of the apparatus shown on this drawing is believed to be correct but the original lampworks may have been altered since the apparatus was installed. The exact position of the apparatus should be verified by the use of a suitable cable location device prior to excavation using suitable hand tools.

A separate record is kept for each service cord but its route is not necessarily shown on this record. It must be assumed that there is a service cable into each property, many columns and street sign, etc. All cables must be treated as being the same provided otherwise by a Liff Energy Supervisor.

The information provided must be given to all people working near the London Electricity apparatus.

FIN 0036T - ASK! PHONE 02701 965797

This plan has been issued for safety purposes in relation to the Electricity Network
do not use for exception purposes more than 3
months after the issue date

PRIMARY CABLES
EXTRA HIGH VOLTAGE™ CABLES (EHV) 22,000 TO 132,000 Volts

Depth normally 750mm cover in carriageway & 600mm cover in footway.
 ---S---S---S---S---S---S---S
 Indicates part of route where cover is less than normal.

Before digging within one metre of these cable routes
Telephone 08701 963797

In order that the Company's apparatus may be located on site and any necessary protection works agreed.

N.B. THRUST BORDERS OR MOLES MUST NOT BE USED WITHIN THE VICINITY OF ANY CABLES BELONGING TO EDF ENERGY WITHOUT FIRST CONTACTING THIS COMPANY.



ADVICE TO CONTRACTORS ON AVOIDING
DANGER FROM BURIED ELECTRICITY
CABLES.

- 1) Do have cable drawings with you on site and check them before you start the excavation.
- 2) Do have a cable locator tool on site and use it to help you.
- 3) Mark out the location of electricity cables.
- 4) Do not use a mechanical excavator within 0.5m of electricity cables.
- 5) Use spades and shovels in preference to other tools.
- 6) Never disturb electricity cables and joints or their protective covers.


REPORTING DAMAGED CABLES
EDF Energy 0800 780078

EDF Energy 0800 780078

These basic safety precautions are explained in detail in the HSE booklet, HSC(G)47 – Avoiding Danger from Underground Services, a copy of which may be obtained from your supervisor or HWSO.



Based upon the Ordnance Survey map by EDF Energy Ltd. by permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationary Office. (C) Crown copyright. (C) EDF Energy Networks (EPN) plc or EDF Energy Networks (SPN) plc each being a distribution licensee under section 6(1)(c) of the Electricity Act 1989. All rights reserved.



IF IN DOUBT ASK

O:\ODD_JOBS\LESYM 17/05/02.

Highways and Street Works Act 1991 has required since August 1997 that at least one person be present on a street work site while work is in progress. This information is meant as a substitute for proper accreditation, but does however provide guidance and precautions that should be adopted before any work is carried out on the public footway. Please note: At least one member of the working party should be streetworks accredited and have this Accreditation available for inspection, if required to produce it

Accidents occur when underground cables are damaged during the course of excavation. Damaged electricity cables can result in an explosion, which can cause serious injury or

death. A footpath in major towns and cities has one or more electricity cables beneath it. Your attention is drawn to the following points:

1. Take drawings with you on site and check them before you start the excavation work. Some cables may not belong to the regional electricity company (EDF Energy East of London) and therefore will not be shown on the drawings. All records are guide only and may not be accurate due to geographical changes e.g. foot path level being increased.

2. Use a cable location device on site e.g. CAT, and use this to help you survey the site before digging. If you don't know how to use a Cable Avoidance Tool, then please refer to your supervisor or supplier/manufacturer, in order to gain training in the competent use of avoidance tools before work commences, if you have not received adequate training, then cable detection being abandoned.

3. Mark the location of electricity cables in accordance with the signals that are obtained from the cable location tool. Remember that:

The cable locator, in the 'power' mode will not always detect the presence of all cables specially if they are not carrying any current at the time. When the cable locator is used along with the signal generator, or in the 'radio' mode, it is more likely that cables not carrying current will be detected.

4. Be aware of overhead power lines and you see if there is anything nearby that would have an electricity service, such as telegraph poles, phone boxes, bus shelters, traffic light control boxes etc. These all will have a small service cable running to them, which can be easily damaged.

5. Do not use the locator during the entire excavation process – you may be only inches from a live cable!

6. Do not use a mechanical excavator within 0.5m of the known presence of an electricity cable. If one is used at any time keep everyone clear of the bucket while it is digging.

7. Use spades and shovels with insulated handles, and preference to other tools such as forks and picks and NEVER throw or spike tools forcibly into the ground.
8. If forks and picks have to be used, then tools with short blunted chisel ended tips should be used. This may be the case if the ground is very hard and the surface needs to be broken up first.
9. If any cables are suspected of being embedded in the concrete that you need to excavate, DO NOT start work until:
 - The cables have been made dead, (likely to require EDF Energy attendance to site) OR
 - A representative of EDF Energy has established and communicated to you an agreed alliterative safe system of work
10. Never assume that cables follow a straight line or that they run at the same depth.
11. Never disturb electricity cables and joints or their protective covers.
12. Always ensure that all exposed cables are adequately supported, e.g. house brick etc, and never use cables or joints as hand holds or steps for gaining entry/exit to an excavation. If necessary protect cables using sandbags, timber shuttering etc.

In the event that a cable is damaged, or that you suspect a cable is damaged (*no matter how slight*):

- Mark the location
- Keep people at a safe distance
- Telephone EDF Energy using one of the following numbers:

When calling, you will need to describe the incident and its exact location, giving the name, address and telephone number of your company. No charge will be made for cable damage site visits where cable repairs are not required.

Emergencies & Electricity supply faults London area:

Residential customers 0800 096 9000 Business customers 0800 096 2255

Emergencies & Electricity supply faults East of England Area: 0800 783 8838

PLEASE NOTE: the basic precautions and advice given here are explained in more detail in the HEALTH AND SAFETY EXECUTIVE PUBLICATION, HS(G) 47-'Avoiding Danger from Underground Services' priced at £7.50 (ISBN 0-7176-7176-1744-0) – available from HSE books and HMSO. ISBN



ADS Sewer Map Key

If you have any queries about the symbols on this key call the relevant number below:

Asset Location Team: 0118 923 6664

**Commercial Drainage
& Water Team: 0118 923 6652**

Common public sewers



Foul:
A sewer designed to convey waste water from domestic and industrial sources to a treatment works.



Surface Water:
A sewer used to convey surface water (eg: rain water from roofs, yards and car parks) to watercourses or rivers.



Combined:
Both surface water and foul sewage flow in the same pipe.

Other public sewers



Joint



Trunk Foul



Trunk Surface Water



Trunk Combined



Abandoned



Storm Relief



Bio-Solids (Sludge)



Vent Pipe



Trade Effluent



Proposed



Culverted Watercourse



Gallery



Foul Rising Main



Surface Water Rising Main



Combined Rising Main



Sludge Rising Main



Other

Sewer Fittings

A feature in a sewer that does not affect the flow of liquid in the pipe. Example: a Vent is a fitting as the function of a vent is to release excess gas.

◆ AV	Air Valve	■ LH	Lamp Hole
○ BS	Blind Shaft	● LS	Lifting Shaft
■ CP	Catch Pit	■ ME	Meter
└ DC	Dam Chase	○ RE	Rodding Eye
└ DF	Double Flushing Tank / Chamber	■ PT	Test Point
└ SF	Single Flushing Tank / Chamber	■ VC	Vent Column
● GP	Gauging Point	■ VT	Vent
□ GU	Gully	■ XX	Other (specified on plan)
□ HB	Hatch Box		

Operational Controls

A feature in a sewer that changes or diverts the flow of liquid in the sewer. Example: A hydrobrake limits the flow of liquid passing downstream.

└ BB	Baffle Board	◎ HY	Hydrobrake
● BD	Backdrop Manhole	■ PI	Petrol Interceptor
└ BV	Butterfly Valve	└ PS	Penstock
└ CL	Clough	└ RV	Reflux Valve
└ DB	Dam Board	└ ST	Step
└ DP	Drop Pipe	└ SV	Sluice Valve
● DS	Drop Shaft	■ TA	Tank
└ FL	Flume	└ WB	Weir Board
└ FV	Flap Valve	└ WW	Weir
└ HW	Headwall	■ XX	Other (specified on map)

End Items

An end symbol is what happens at the start or end of a sewer pipe. Examples: an Undefined End at the start of a sewer indicates that Thames Water has no knowledge of the position of the sewer upstream of that symbol, and Outfall on a surface water sewer indicates that pipe empties into a stream or river.

└ STW	Effluent Discharge	└ Inlet	Undefined End
└ Soakaway			
└ Outfall			

Other Symbols

Symbols used on maps which do not fall under other general categories.

◆ Sewage Treatment Works	△ Summit
▲ Pumping Station	⚡ Change of characteristic indicator (C.O.C.I.)

+ IL Invert Level

Areas

Lines denoting areas of underground surveys, etc.

□ Building over Case (BOC No.) or Low Lying Land (LLL No.)	□ Licence Area
□ Drawing Area	□ Survey Area
□ Sewage Treatment Works or Pumping Station	□ Area under Adoption
□ Retention Tank area	□ Other Area (Specified on plan)

Private Sewer Types

└ Foul	
└ Surface Water	
└ Combined	
└ Highway Drain	
└ Culvert	

NOTES:

- 1) All levels associated with digital plans are to Ordnance Datum Newlyn.
- 2) All measurements on digital maps are metric.
- 3) Arrows (on gravity fed sewers) or flecks (on rising mains) indicate direction of flow.
- 4) For symbols referred to as 'Other' on this key, please see digitised plan for further information.
- 5) Most private pipe work is not shown on our maps, as in the past, this information has not been recorded.

- 6) -9999.00 or 0 on manhole level indicates that data is unavailable.

- 7) The text appearing alongside a sewer line indicates the internal diameter of the pipe in millimetres. Text next to a manhole indicates the manhole reference number and should not be taken as a measurement. When cover and invert levels appear on a plan they are clearly prefixed by 'CL' and 'IL'. If you are unsure about any text on the plan, please contact the relevant team on the number at the top of this key.



ADE/222479

BAT/5780/NPB/719
ONE CALL UK - [REDACTED]
29th December 2004

20/12

MOLESEYE LTD
WASHINGTON COURT
WASHINGTON LANE
EDINBURGH
EH11 2HA

Dear Sirs,

>CHARTER AVE NEWBURY PARK ILFORD REDBRIDGE

In response to your enquiry dated 17th December 2004 concerning the above property, I am able to comment as follows:-

Please find enclosed a map on which the approximate position of this companies sewers are shown. If you require further information please phone 0845 9200 800 or alternatively our Service desk on 0845 8502777.

*** EMERGENCY NUMBER IF YOU SHOULD HIT OUR PIPEWORK: 0845 9200 800***
Please also use this number if you require a site visit from this Company.

With regard to fresh water supply, this site falls within the boundaries of another water company. For your information, their address is provided below:

Essex and Suffolk Water PLC
Hall Street
Chelmsford
Essex
CM2 0HH Tel: 0845 7820 111

The replies contained in this letter are given following inspection of the public service records available to this Company. No responsibility can be accepted for any error or omission in the replies.

Yours faithfully,

(
[REDACTED]
Asset Location Services.



The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

100 metre intervals

EAGLE hardcopy facility - Normal Map.
The plot is centred on (544857 , 187397), which is in TQ4487SE. Printed on 21 December 2004 at 20:43:48 by LANGELL.

Comments:
CLEAN WATER SUPPLIED BY ESSEX AND SUFFOLK WATER

position of apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and st lished on site before any works are undertaken.

Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates no survey information is available.

t (545028,187349)	there is a MANHOLE with SHORT NUMBER=0301	COVER=	13.38	INVERT=	10.79
t (545026,187347)	there is a MANHOLE with SHORT NUMBER=0302	COVER=	13.46	INVERT=	11.60
t (545043,187568)	there is a MANHOLE with SHORT NUMBER=0501	COVER=	13.83	INVERT=	11.98
t (545043,187567)	there is a MANHOLE with SHORT NUMBER=0502	COVER=	13.83	INVERT=	12.43
t (544835,187258)	there is a MANHOLE with SHORT NUMBER=8201	COVER=	13.10	INVERT=	8.48
t (544801,187259)	there is a MANHOLE with SHORT NUMBER=8202	COVER=	13.01	INVERT=	8.44
t (544898,187240)	there is a MANHOLE with SHORT NUMBER=8203	COVER=	14.41	INVERT=	12.27
t (544894,187241)	there is a MANHOLE with SHORT NUMBER=8204	COVER=	14.42	INVERT=	12.03
t (544833,187292)	there is a MANHOLE with SHORT NUMBER=8205	COVER=	13.47	INVERT=	10.87
t (544811,187293)	there is a MANHOLE with SHORT NUMBER=8206	COVER=	13.54	INVERT=	11.52
t (544858,187281)	there is a MANHOLE with SHORT NUMBER=8207	COVER=	13.30	INVERT=	9.94
t (544820,187295)	there is a MANHOLE with SHORT NUMBER=8209	COVER=	13.55	INVERT=	12.26
t (544830,187295)	there is a MANHOLE with SHORT NUMBER=8210	COVER=	13.42	INVERT=	12.21
t (544882,187272)	there is a MANHOLE with SHORT NUMBER=8211	COVER=	13.31	INVERT=	11.98
t (544847,187252)	there is a MANHOLE with SHORT NUMBER=8212	COVER=	13.00	INVERT=	8.56
t (544809,187396)	there is a MANHOLE with SHORT NUMBER=8301	COVER=	14.63	INVERT=	11.75
t (544835,187310)	there is a MANHOLE with SHORT NUMBER=8302	COVER=	13.17	INVERT=	11.38
t (544810,187493)	there is a MANHOLE with SHORT NUMBER=8401	COVER=	13.91	INVERT=	12.09
t (544806,187493)	there is a MANHOLE with SHORT NUMBER=8402	COVER=	13.94	INVERT=	12.63
t (544816,187571)	there is a MANHOLE with SHORT NUMBER=8501	COVER=	14.38	INVERT=	12.51
t (544814,187568)	there is a MANHOLE with SHORT NUMBER=8502	COVER=	14.35	INVERT=	12.92
t (544911,187222)	there is a MANHOLE with SHORT NUMBER=9201	COVER=	14.21	INVERT=	8.70
t (544971,187207)	there is a MANHOLE with SHORT NUMBER=9202	COVER=	12.05	INVERT=	8.80
t (544914,187296)	there is a MANHOLE with SHORT NUMBER=9205	COVER=	13.05	INVERT=	11.40
t (544999,187272)	there is a MANHOLE with SHORT NUMBER=9206	COVER=	12.77	INVERT=	10.93
t (544912,187298)	there is a MANHOLE with SHORT NUMBER=9207	COVER=	13.03	INVERT=	11.75
t (544998,187275)	there is a MANHOLE with SHORT NUMBER=9208	COVER=	12.78	INVERT=	11.30
t (544902,187266)	there is a MANHOLE with SHORT NUMBER=9209	COVER=	-9999.00	INVERT=	-9999.00
t (544922,187325)	there is a MANHOLE with SHORT NUMBER=9301	COVER=	13.26	INVERT=	11.71
t (544986,187379)	there is a MANHOLE with SHORT NUMBER=9302	COVER=	13.78	INVERT=	11.38
t (544982,187376)	there is a MANHOLE with SHORT NUMBER=9303	COVER=	13.88	INVERT=	11.84
t (544941,187567)	there is a MANHOLE with SHORT NUMBER=9501	COVER=	14.24	INVERT=	12.50
t (544941,187566)	there is a MANHOLE with SHORT NUMBER=9502	COVER=	14.24	INVERT=	12.69
t (544897,187275)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (545047,187556)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (545044,187554)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (545042,187539)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (545041,187543)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (544941,187280)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (544944,187281)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (544881,187279)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (545018,187558)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (545017,187543)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (545010,187207)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
t (545014,187223)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
t (545014,187243)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
t (544988,187542)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
t (544946,187590)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
t (545039,187367)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
t (545019,187259)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
t (544718,187237)	there is a MANHOLE with SHORT NUMBER=7201	COVER=	11.87	INVERT=	10.00
t (544727,187232)	there is a MANHOLE with SHORT NUMBER=7202	COVER=	12.06	INVERT=	8.29
t (544774,187243)	there is a MANHOLE with SHORT NUMBER=7203	COVER=	13.89	INVERT=	8.38
t (544705,187276)	there is a MANHOLE with SHORT NUMBER=7204	COVER=	12.16	INVERT=	10.19
t (544717,187221)	there is a MANHOLE with SHORT NUMBER=7205	COVER=	11.92	INVERT=	10.50
t (544708,187228)	there is a MANHOLE with SHORT NUMBER=7206	COVER=	11.82	INVERT=	10.75
t (544717,187233)	there is a MANHOLE with SHORT NUMBER=7207	COVER=	11.82	INVERT=	10.49
t (544728,187229)	there is a MANHOLE with SHORT NUMBER=7208	COVER=	12.13	INVERT=	10.03
t (544766,187240)	there is a MANHOLE with SHORT NUMBER=7209	COVER=	13.67	INVERT=	9.92
t (544781,187231)	there is a MANHOLE with SHORT NUMBER=7210	COVER=	11.90	INVERT=	9.92
t (544767,187263)	there is a MANHOLE with SHORT NUMBER=7211	COVER=	0.00	INVERT=	-9999.00
t (544702,187277)	there is a MANHOLE with SHORT NUMBER=7212	COVER=	0.00	INVERT=	-9999.00
t (544709,187302)	there is a MANHOLE with SHORT NUMBER=7301	COVER=	12.44	INVERT=	11.06
t (544720,187333)	there is a MANHOLE with SHORT NUMBER=7302	COVER=	12.82	INVERT=	11.13
t (544723,187335)	there is a MANHOLE with SHORT NUMBER=7303	COVER=	12.84	INVERT=	10.51
t (544723,187350)	there is a MANHOLE with SHORT NUMBER=7304	COVER=	12.97	INVERT=	10.59
t (544713,187398)	there is a MANHOLE with SHORT NUMBER=7306	COVER=	13.28	INVERT=	11.31
t (544770,187399)	there is a MANHOLE with SHORT NUMBER=7307	COVER=	13.40	INVERT=	11.62
t (544711,187395)	there is a MANHOLE with SHORT NUMBER=7308	COVER=	13.26	INVERT=	12.38
t (544765,187395)	there is a MANHOLE with SHORT NUMBER=7309	COVER=	13.36	INVERT=	12.25
t (544680,187418)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (544681,187407)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (544697,187293)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (544730,187389)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (544782,187446)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
t (544795,187406)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00

The position of apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and published on site before any works are undertaken.

Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates no survey information is available.

At (544783,187409)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
At (544735,187299)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
At (544765,187452)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
At (544730,187376)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
At (544727,187320)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
At (544715,187268)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
At (544682,187293)	there is a MANHOLE with SHORT NUMBER=	COVER=	-9999.00	INVERT=	-9999.00
At (544703,187244)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
At (544738,187249)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
At (544780,187479)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
At (544806,187430)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
At (544935,187542)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
At (545019,187543)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
At (544789,187506)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
At (544795,187506)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00
At (544801,187505)	there is a MANHOLE with SHORT NUMBER=	COVER=	0.00	INVERT=	0.00

Atkins Telecoms
PO Box 290
220 Aztec West
Park Avenue
Almondsbury
BRISTOL BS32 4SY

Tel: 01454 288808
Fax: 0870 2403012
Email: osm.enquiries@atkinsglobal.com

MOLESEYE
WASINGTON COURT
WASHINGTON LANE
EDINBURGH
EH11 2HA

Our Ref: NRSWA/544/51/0622
Your Ref: BAT/5780/NPB/719

20/12

Attention: [REDACTED]

Date: 8/12/04

Dear Sirs,

**New Roads and Street Works Act 1991
C2 Plant Enquiry – Plant Not Affected**

Thank you for your correspondence dated 6/12/04 regarding a Plant Enquiry/C2 Diversionary Works Enquiry at CHARTER AVENUE for proposed WORKS.

51 Degrees Limited do not have apparatus in the vicinity of your proposed scheme.

Yours Faithfully,

OSM, UK and Ireland
Acting as Agent for and on behalf of 51 Degrees Limited.

Please note. To enable us to process your application as quickly as possible, please ensure that you include a post code and/or an Ordnance Survey Grid Reference. Thank you for your co-operation.



PRINTING PROCESS ACTIVATED
SELECT YOUR OPTIONS FROM THE PRINT
DIALOG
(THIS WINDOW WILL CLOSE AUTOMATICALLY)

Linesearch.org

Thank you for your enquiry: LS-1061343-118

This enquiry result is valid for 28 days only from the date of enquiry and is based on the confirmed information you entered. If the location of the work changes then a further enquiry must be made. Should the work not be undertaken within 28 days of the enquiry then a further enquiry must be made.

Enquirer details

Name: [REDACTED]

Company: Moleseye One Call

Email: [REDACTED]@moleseye.com

Enquiry details

Location: OS grid reference (544842, 187453)

Estimated start date: 17-01-2005

Type of work: Development projects - Commercial/industrial

Distance covered: 500 meters

This enquiry is not in the zone of interest of any of the following Operators:

* BPA	NOT IN ZONE OF INTEREST
* Esso Petroleum Company Limited	NOT IN ZONE OF INTEREST
* Government Pipelines & Storage System	NOT IN ZONE OF INTEREST
* Manchester Jetline Limited	NOT IN ZONE OF INTEREST
* Mainline Pipelines Limited	NOT IN ZONE OF INTEREST

*Please quote the LineSearch enquiry reference number in *all* correspondence*



This service is brought to you by Fisher German ©2004
System by eShopworks

BGCL Reference : ENQ5720
Your Reference :

Moleseye Ltd
Washington Court
Washington Lane
Edinburgh
EH11 2HA

02 December 2004

Dear 

Thank you for your enquiry regarding the location of our plant and/or services in relation to :


Bat/5780/ Npb/719 *
Bat/6810/ Cls/14
Bat/2470/ Rso/58


20/12

I can confirm that 'British Gas Connections Ltd' does not have plant and/or services in the area indicated in your letter.

I would suggest that you contact 'BG Transco' who may have plant in the area.

Yours faithfully,



 Asset Manager



Woolpit Business Park
Woolpit, Bury St Edmunds
Suffolk IP30 9UQ

Gas Transportation Company

Sales & Administration: Tel: 01359 240363 Fax: 01359 240188
Operations: Tel: 01359 244066 Fax: 01359 244046

PLANT ENQUIRY RESPONSE 11928


Dear Sirs

In reply to your communication reference number BAT/5780/NPB/719 dated 27/11/04 of your intention to execute works. GTC has no apparatus in the vicinity of your proposed works.

Please note other Gas Transporters may have apparatus in this area and you should ensure that all transporters have been consulted.

Yours faithfully

The Gas Transportation Company Ltd



Planning Assistant



The Gas Transportation Company Ltd, is a Company registered in Guernsey, Channel Islands, registered number 29431.
It is a wholly owned subsidiary of the International Energy Group.

**thus**TM**FAX**

Date December 2, 2004

Number of pages including cover sheet 1

TO Moleseye Ltd

Washington Court
Washington Lane
Edinburgh
EH11 2HA

Phone 0845 140 0271

Fax Phone 0131 539 7310

FROM:

Plant Protection & Streetworks Co-
ordination Group
Pavilion 4
1 - 2 Berkeley Square
29 Berkeley Street
Glasgow G3 7HR

Email [REDACTED]@thus.net

Phone 0141 566 3434

Fax Phone 0141 566 3954

REMARKS: ☐ Urgent ☐ For your review ☐ Reply ASAP ☐ Please Comment

FAO [REDACTED] 20/12

RE- BAT/4605/LCB/2, BAT/3935/HIW/4, BAT/5780/NPB/719, BAT/4715/MOL1/3

After consulting our GIS System, I am unaware of any Thus plant which
would be affected by your works.Regards,
[REDACTED]

Plant Information Request View

Page 1 of 2

REC'D

00 000 000

5769D

Plant Information Request View



Plant Information Request		
Transaction No : BAT/6780/NPB/718	Project Ref :	Status : In Progress
Name Moleseye One Call	Company Moleseye One Call	Address Washington Court, Washington Lane, Edinburgh EH11 2HA
Phone No 0131 539 7300 Ext	Fax No 0131 539 7310 Email Address	
Respond By Date 20/12/2004	Response Required Plans Required	Date Of Issue 27/11/2004 12:32:00
Map		
Location of Works		
Charter Avenue, Newbury Park, ILFORD, REDBRIDGE		
Specific Location bridge over dismantled railway south east off Charter Avenue and north off Benton Road	Start East 544785	Start North 187540
	End East 544925	End North 187390
Please Send Plant Information To		
Name Moleseye One Call	e-mail	Address Washington Court, Washington Lane, Edinburgh EH11 2HA
Phone No 0131 539 7300 Ext	Fax No	
Comments		
Proposed Works Excavation of inspection pit by hand in the verge. (0.50m by 0.50m)		Comments All service plans required.

Signed:..... Date:.....

connect

Ocean Park House
East Tyndall Street
Cardiff CF24 5GT
Tel: 029 2031 4000
Fax: 029 2031 4030

Ref No: 5769D

With regard to your enquiry, I confirm that Independent Pipelines Ltd or Quadrant Pipelines Ltd do not have any apparatus within the immediate proximity of your proposed works.

If you require any further assistance please do not hesitate to contact me on 029 2031 4000 Ext. No:.....4163.....
1/12/04



Your ref: BAT/5780/NPB/719
Our ref: TASS/AD/NRSWA/ENQ/14

Moleseye One Call
Washington Court
Washington lane
Edinburgh
EH11 2HA

29/12

Street Management

Windsor House
42-50 Victoria Street
London SW1H 0TL

Phone 020 7343 5000
www.tfl.gov.uk

6 December 2004

Dear Sir / Madam

PLANT ENQUIRY: Charter Avenue, Newbury Park, Ilford, Redbridge

Thank you for your facsimile dated 2 December 2004.

Our records show no traffic control equipment within the site of your anticipated works.

Should you vary the location of the works please inform us so that further checks can be made.

If you require further information, please contact [REDACTED] on (020) [REDACTED]

Yours faithfully

[REDACTED]

NRSWA Systems Manager

TfL STREET MANAGEMENT

Email: [REDACTED]@streetmanagement.org.uk

Direct line: (020) [REDACTED]

Fax: (020) 7027 9760

Our Ref: TW/TNN/38143
Dealt By: [REDACTED]
Contact Number: (08708) 883137
Your Ref:

Date: 04-Jan-05

Telewest Broadband

TNN Plant Enquiries, Scimitar Park, Courtauld
Road, Basildon, Essex, SS13 1ND

Tel: 0870 888 3137

Fax: 01268 468155

Email: twsegenadmin@telewest.co.uk

BIAT/5780/NPB/719

20/12

[REDACTED]
Moleseye One Call
Washington Court
Washington Lane
Edinburgh
EH11 2HA

Location - Charter Avenue

Thank you for your enquiry dated 16 December 2004 regarding the above location.

Telewest plant should not be affected by your proposed work and no strategic additions to our existing network are envisaged in the immediate future.

However you should be aware that elements of our network are built in response to customer orders so this situation can change.

This information is only valid on the date of issue. If your start date is 3 months or more from the date of this letter, please re-apply for updated information.

Yours faithfully


[REDACTED]
TNN Plant Enquiries, Administration Centre SE

Plant Information Request View

Page 1 of 2

Plant Information Request View

moleseye

Plant Information Request		
Transaction No : BAT/6780/NPB/719	Project Ref :	Status : In Progress
Name Moleseye One Call	Company Moleseye One Call	Address Washington Court, Washington Lane, Edinburgh EH11 2HA
Phone No 0131 539 7300 Ext	Fax No 0131 539 7310 Email Address	
Respond By Date 20/12/2004	Response Required Plans Required	Date Of Issue 27/11/2004 12:32:00
Map 		
Location of Works		
Charter Avenue, Newbury Park, ILFORD, REDBRIDGE		
Specific Location bridge over dismantled railway south east off Charter Avenue and north off Benton Road	Start East 544785 End East 544925	Start North 187540 End North 187390
Please Send Plant Information To		
Name Moleseye One Call	e-mail	Address Washington Court, Washington Lane, Edinburgh EH11 2HA
Phone No 0131 539 7300 Ext	Fax No	
Comments		
Proposed Works Excavation of inspection pit by hand in the verge. (0.50m by 0.50m)		Comments All service plans required.


14/12/04

Canon

streetmap

BAT/5780/NPB/719

Wish you could control



Map Data Copyright Collins Bartholomew 2003

SIGMA TEK

Sigmathek Limited
Suite 1
New Road Business Estate
New Road
Ditton, Aylesford
Kent ME20 6AF
Tel: +44 (0) 1732 874422
Fax: +44 (0) 1732 229430

FAX

To: Moleseye One Call
Washington Court
Washington Lane

From: Level 3 Communications Ltd
Plant Protection
C/O Sigmatek Ltd

Fax: 0131 539 7310

Pages: 1 of 1

Phone: 0131 539 7300

Date: 01 December 2004

☐ **Urgent** ☐ **For Review** ☐ **Please Comment** ☐ **Please Reply** x **Please Recycle**

Your Ref.: BAT/5780/NPB/719

Our Ref.: 0412 035

Attn: [REDACTED]

RE: Plant Enquiry at Charter Avenue, Newbury Park, Ilford, Redbridge

Level 3 Communication Limited is a licensed Statutory Utility.

**We have reviewed your plans and have determined that
Level 3 Communications has No Apparatus In the areas concerned.**

If you have any further queries, please do not hesitate to call.

Plant Information Request View


Page 1 of 2

Plant Information Request View

moleseye

Plant Information Request			
Transaction No : BAT/5780/NPB/719		Project Ref :	
Name Moleseye One Call		Status : In Progress	
Company Moleseye One Call		Address Washington Court, Washington Lane, Edinburgh EH11 2HA	
Phone No 0131 539 7300 Ext		Fax No 0131 539 7310	
Email Address		Date Of Issue 27/11/2004 12:32:00	
Respond By Date 20/12/2004		Response Required Plans Required	
Map			
Location of Works			
Charter Avenue, Newbury Park, ILFORD, REDBRIDGE			
Specific Location bridge over dismantled railway south east off Charter Avenue and north off Benton Road		Start East 544785	
		Start North 187540	
		End East 544925	
		End North 187390	
Please Send Plant Information To			
Name Moleseye One Call		e-mail	
Address Washington Court, Washington Lane, Edinburgh EH11 2HA			
Phone No 0131 539 7300 Ext		Fax No	
Comments			
Proposed Works Excavation of inspection pit by hand in the verge. (0.50m by 0.50m)		Comments All service plans required.	

The Corporation of London
have no plant in this area



21/12/04



2nd December 2004

Attn. One Call Dept

Moleseye Ltd
Washington Court
Washington lane
Edinburgh
EH11 2HA

Dear Sir/Madam,


I refer to your New Roads and Street Works Act 1991 submissions for your proposed works at the following locations:

Ref	Grid	Site
AF7/5600/D4452	524150, 524330, 181270, 181345	Ladbroke Grove Station
AF7/5780/D4764	544910, 545110, 190600, 190720	Forest Road, Hainault Road, Ilford, Redbridge
BAT/4606/LCB/2	405265, 405425, 280427, 280252	Pershore Road, Bournville, Birmingham, West Midlands
BAT/3936/HIW/4	417520, 417695, 188857, 188692	Kingsdown Road, Swindon, Swindon Borough Coucil
BAT/5780/NPB/719	544785, 544925, 187540, 187890	Charter Avenue, Newbury Park, Ilford, Redbridge
BAT/2470/RSO/58	492535, 492745, 300645, 300467	High street Morcott, Rutland UA
BAT/4715/MDL1/3	422570, 422855, 420250, 420082	Calder Road, Ravensthorpe, Dewsbury, Kirklees
BAT/6810/CLS/14	249230, 249415, 362210, 362010	A4085 - Caethro roundabout, waunfawr, Gwynedd


I can confirm that E S Pipelines Ltd have no plant in the vicinity of your proposed works at these locations.

If you wish to discuss this matter further please contact me on [REDACTED] or [REDACTED]

Yours faithfully



BT Maps by email Plant Information Reply















IMPORTANT WARNING:

Information regarding the location of BT apparatus is given for your assistance and is intended for general guidance only. No guarantee is given of its accuracy. It should not be relied upon in the event of excavations or other works being made near to BT apparatus which may exist at various depths and may deviate from the marked route.

Reproduced from an OS map by permission of Controller HMSO. Crown Copyright Reserved, with British Telecommunications plc data added. Copyright British Telecommunications plc

FOR FREE ON SITE LOCATION & MARKING SERVICE
CALL DIAL BEFORE YOU DIG 0800 917 3993

KEY TO BT SYMBOLS

	UNDERGROUND PLANT		CABINET
	OVERHEAD PLANT		BURIED JOINT
	JOINT BOX		JOINTING POST
	DISTRIBUTION POINT		PROPOSED U/G
	MANHOLE		PROPOSED O/H
	POLE		PROPOSED BOX

Other proposed plants shown using dashed lines. BT symbols not listed above may be disregarded. Existing BT plant may not be recorded. Information valid at the time of preparation.

BT ref WANK13404L

Map reference (centre) TQ485087450

Issued: 27/11/04 13:43:56

Atkins Telecoms
PO Box 290
220 Aztec West
Park Avenue
Almondsbury
BRISTOL BS32 4SY

Tel: 01454 288808
Fax: 0870 2403012
Email: osm.enquiries@atkinsglobal.com

Moleseye One Call

SRWR Operations Centre

Washington Court, Washington Lane

Edinburgh

EH11 2HA

Our Ref: NRSWA/544/243094

YourRef: BAT/5780/NPB/719

F.A.O:

Date: 30 November 2004

Dear Sirs,

New Roads and Street Works Act 1991

C2 Plant Enquiry re: Highway Land only - Plant Affected

Thank you for your enquiry regarding works at CHARTER AVENUE, for proposed WORKS.

Cable and Wireless UK have apparatus in the vicinity of your proposed scheme. We have enclosed plans showing the approximate position of the apparatus, please note the disclaimer on the plans.

A copy of the current special requirements guidance process OSM.060, relating to the protection of external network apparatus when working in it's vicinity, is available upon request.

Diversionary works may be necessary if the existing line of the highway / railway or it's levels are altered, where apparatus is affected.

Where apparatus is affected and requires diversion, you must submit draft details of the proposed scheme with a written request for a 'C3 Budget Estimate' to the address below. These estimates should be provided normally within 20 working days from receipt of your written request. Please quote our reference above when requesting a C3 Budget Estimate. Failure to submit your request to the address below may lead to delays in processing it.

'C3 Diversionary Works Budget Estimates Coordinator'

Atkins Telecoms
PO Box 290
220 Aztec West
Park Avenue
Almondsbury
BRISTOL BS32 4SY

Please note: If your enquiry relates to works affecting rail transport authority land, we have assumed that only apparatus in the highway may be affected. Please resubmit your enquiry clearly stating that the works affect railway, in order that we can check against apparatus records for the railway.

Yours Faithfully,

OSM, U.K. and Ireland

Acting as agent for and on behalf of Cable and Wireless UK

Please note. To enable us to process your application as quickly as possible, please ensure that you include a post code and an Ordnance Survey Grid Reference. Thank you for your co-operation.



**CABLE & WIRELESS COMMUNICATIONS
PLANT NETWORK**

DRAWING TITLE:
CHARTER AVENUE

PROJECT TITLE:
bat/5780/npb/719

OS 1250 ref. C&W Ref.
tq4487ne tq48nw/050

NOTES:

The information shown on this plan is for indication only. No warranty is made as to its accuracy. This plan must not be relied upon in the event of excavation or other works carried out in the vicinity of Cable & Wireless UK Ltd plant. No liability of any kind whatsoever is accepted by Cable & Wireless UK Ltd, its servants, or agents, for any error or omission in respect of information contained on this plan. The actual position of underground services must be verified and established on site before any mechanical plant is used.




Cable & Wireless UK Ltd.
Great Park Road
Almondsbury
Bristol
BS32 4QV

Based upon the Ordnance Survey map reproduced by Cable & Wireless Communications by permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office. Crown Copyright Cable & Wireless Communications CC38012C/0001


SCALE 1: 2500 ON A3

DRAWING NO:	Sheet: __ of __	ISSUE: ...
-------------	--------------------	------------



DR4
225637
09/08/04

SCALE: 1 : 500		<p>LP MAINS</p> <p>MP MAINS</p> <p>IP MAINS</p> <p>LHP MAINS</p> <p>NHP MAINS</p>	<p>This plan shows those pipes owned by Transco plc or the relevant Gas Distribution Network in their roles as Licensed Gas Transporters (GT). Gas pipes owned by other GTs, or otherwise privately owned, may be present in this area. Information with regard to such pipes should be obtained from the relevant owners. The information shown on this plan is given without warranty, the accuracy thereof cannot be guaranteed. Service pipes, valves, syphons, stub connections, etc. are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Transco plc, the relevant Gas Distribution Network, or their agents, servants or contractors for any error or omission. Safe digging practices, in accordance with HS(G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that this information is provided to all persons (either direct labour or contractors) working for you on or near gas apparatus. The information included on this plan should not be referred to beyond a period of 28 days from the date of issue.</p>	Desktop MAPS Version 4.3.0	
USER ID: cb049				Hutton	
DATE: 27/01/2005				This plan is reproduced from or based on the OS map by Transco plc, with the sanction of the controller of HM Stationary Office. Crown Copyright Reserved.	
NRSWA RESPONSE					
GRID REFERENCE : 544840, 187383, TQ4487					
Some examples of Plant Items					
Valve	Depth of Cover	Syphon	Diameter Change	Material Change	



SCALE: 1 : 1250		LP MAINS		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		50m	
USER ID: KK005		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		Approximate scale 1 : 1250 printed on A3 Colour Portrait	
DATE: 26/01/2005		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		0m	
NRSWA RESPONSE		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		50m	
GRID REFERENCE : 544938, 187484, TQ4487		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		50m	
Some examples of Plant Items:		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		50m	
Valve		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		50m	
Depth of Cover		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		50m	
Syphon		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		50m	
Diameter Change		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		50m	
Material Change		MP MAINS		IP MAINS		LHP MAINS		NHP MAINS		NHP MAINS		50m	

This plan shows those pipes owned by Transco plc or the relevant Gas Distribution Network in their roles as Licensed Gas Transporters (GT). Gas pipes owned by other GTs, or otherwise privately owned, may be present in this area. Information with regard to such pipes should be obtained from the relevant owners. The information shown on this plan is given without warranty, the accuracy thereof cannot be guaranteed. Service pipes, valves, syphons, stub connections, etc. are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Transco plc, the relevant Gas Distribution Network, or their agents, servants or contractors for any error or omission. Safe digging practices, in accordance with HSG47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that this information is provided to all persons (either direct labour or contractors) working for you on or near gas apparatus. The information included on this plan should not be referred to beyond a period of 28 days from the date of issue.

Desktop MAPS Version 4.3.0

Hutton

This plan is reproduced from or based on the OS map by Transco plc, with the sanction of the controller of HM Stationery Office. Crown Copyright Reserved.

Appendix C - Trial Pit and Metal Test Results



BRIDGE INVESTIGATION

BE4 ASSESSMENT PROGRAMME

**STRUCTURAL
SOILS LTD**

CONTRACT NO. 47101

BRIDGE NPB/719

Site Description

The investigation on Bridge NPB/719 was carried out for and on the instructions of Jacobs. The bridge is located on Benton Road, Seven Kings, Redbridge, London at National Grid Reference TQ448874.

The bridge carries Benton Road over a dismantled railway and comprises of single spanning longitudinal steel girders with brick jack arches. The investigation was carried out to provide information for the structural assessment of the bridge.

Sitework was undertaken on 12th January 2005.

Fieldwork

1 no. inspection pit was excavated by hand to locate the top flange of a steel girder and 1 no. metal sample, <25mm x 25mm in size, was taken from a position specified by Jacobs. The sample was labelled and sent to a UKAS accredited laboratory for testing.

Laboratory Testing

The chemical composition and grading of the sample was determined using combustion and ICP OES techniques. The results are presented overleaf.




STRUCTURAL SOILS

TRIAL PIT LOG

Contract BE4 Bridges - NPB/719		Client Jacobs		Trialpit No TP01
Job No 47101	Date 12.1.05	Ground Level (m AOD) ---	Co-Ordinates ---	Sheet 1 of 1

Samples and In-situ Tests				Water	Description of Strata	Depth (Thickness)	Legend
Depth	No	Type	Results				
					MADE GROUND : Concrete paving.	0.05	
					MADE GROUND : Brown slightly silty fine to coarse SAND.	0.23	
					MADE GROUND : Brown slightly silty to silty fine to coarse SAND and sub angular to rounded fine to coarse GRAVEL of flint. Occasional cobbles of brick. Occasional pockets of sandy clay.	0.69	
					MADE GROUND : Asphalt sealant.	0.72	
					Trial Pit ends at 0.72m on top flange.		

Plan (Not to Scale)		General Remarks		
<p>No Bearing Taken</p>		<ol style="list-style-type: none">1. Groundwater : None Encountered2. Stability : All sides stable.3. Similarity : All sides similar.4. Excavation : Easy by hand.5. Top flange located 1.30m from parapet, width of flange 356mm.		
All dimensions in metres Scale 1:25	Method Hand Dug	Logged By 	Checked By 	



SHEFFIELD
TESTING LABORATORIES

50 - 56 Nursery Street, Sheffield, S3 8GP. U.K.
Telephone: 0114 272 6581 Fax: 0114 272 3248 e-mail: hq@sheffieldtesting.com

TEST CERTIFICATE



Date. 28 January 2005
Serial No. 5010680
Page 1 of 1 Pages

ORDER NO. 60/MD/3087

OUR REF AB/AJH

CLIENT: STRUCTURAL SOILS LTD
THE POTTERIES
POTTERY STREET
CASTLEFORD
WEST YORKSHIRE
WF10 1NJ

Results of Chemical Analysis of Sample,

<i>STL Test No.</i>	A694
<i>Sample Identification</i>	NPB/719
	Mass %
<i>Carbon</i>	0.085
<i>Silicon</i>	0.11
<i>Manganese</i>	0.30
<i>Phosphorus</i>	0.29
<i>Sulphur</i>	0.055
<i>Chromium</i>	<0.02
<i>Molybdenum</i>	<0.02
<i>Nickel</i>	0.06

Determined by Combustion & ICP OES Techniques.

Sample A694 is wrought iron with unusually high manganese.

Certified

Authorised Signatory

Appendix D - Form AA

FORM 'AA' (BRIDGES)**GC/TP0356**

ELR/ Bridge No NPB/719

Appendix: 4

Issue: 1

Revision: B (Nov 2000)

APPROVAL IN PRINCIPLE FOR ASSESSMENT**Bridge/Line Name:** Benton Road, Ilford / Newbury Park Branch**ELR/Bridge No.** NPB/719**Brief Description of Existing Bridge:****(a) Span Arrangement**

A single span simply supported bridge, clear square span 7.71 m, with zero skew.

(b) Superstructure Type

The deck consists of 9 No. longitudinal wrought iron riveted plate girders at 5'-2" (1580mm) centres with brick jack arches spanning between the girders.

(c) Substructure Type

Abutments and wingwalls are constructed in brick. The girders are supported on discrete sandstone bearing blocks. The bridge has been infilled to soffit level on the north side and to within 1.4m of the underside of the girders on the south side

(d) Planned highway works/modifications at this site

None

(e) Road designation class and whether classed as a heavy load route

The bridge carries a class "C" urban road. Carriageway width is 8.17m with kerbed pavements each side approximately 2.05m wide.

The bridge was given an abnormal load rating of 110 tons in a 1970 assessment, but it is not known if the road is currently classed as a heavy load route.

(f) Any other requirements

None

Assessment Criteria**(a) Loadings and Speed**

Section sizes used to calculate dead loads obtained from site measurements with reference to previous assessments. (See Jacobs report "VAR9-1220 BE4 Assessment Programme – Assessment and

FORM 'AA' (BRIDGES)**GC/TP0356**

ELR/ Bridge No NPB/719

Appendix: 4

Issue: 1

Revision: B (Nov 2000)

APPROVAL IN PRINCIPLE FOR ASSESSMENT

Inspection Report – Bridge Ref.: NPB/719"). Vehicle loading obtained from and applied in accordance with BE4. Standard BE4 loading representative of 24 ton vehicles will be assessed.

(b) Codes to be used

BE4 - "The Assessment of Highway Bridges for Construction and Use Vehicles" Ministry of Transport, 1967 (with amendments to 1969).

BS 153: Parts 3B & 4: 1958 "Steel Girder Bridges" British Standards Institution (with amendments to 12 Sept. 1968).

(c) Proposed Method of Structural Analysis

Capacities will be calculated using estimates of reduced section sizes where corrosion is present, in particular the effective girder flange areas identified in Table 5A of the Inspection Report. Consequently, a general condition factor is not applied.

The bridge complies with the construction types listed in BE4 Clause 303 (c) (i.e jack arches), which allows the quick assessment method to be used. However, additional checks may be required on the internal girders close to one third span, because this is where corrosion is most prevalent.

The external girders will be checked under dead load only as there is a girder between the edge girders and the carriageway. Compression buckling of the top flange of the edge girders will be considered based on the girders being partially restrained against lateral bending. (Full details of the girder end arrangement are not available.) The internal girders are considered to be fully restrained by the concrete infill.

Determination of the adequacy of the jack arches will be based upon the empirical method described in Bridgeguard 3 Current Information Sheet No 22 (Pro-forma for the empirical assessment of brick, masonry and concrete jack arches and associated ties.)

BRB (Residuary) Limited	Group Standard
--------------------------------	-----------------------

FORM 'AA' (BRIDGES)

GC/TP0356

ELR/ Bridge No NPB/719

Appendix: 4

Issue: 1

Revision: B (Nov 2000)

APPROVAL IN PRINCIPLE FOR ASSESSMENT

Senior Civil Engineer's Comments

None

[The following section is crossed out with a diagonal line]

Proposed Category for Independent Check

Superstructure *I*

Substructure *I*

Name of Checker suggested if Cat 2 or 3 *[Signature]*

Category 1

The above assessment, with amendments shown, is approved in principle:

Signed *[Redacted Signature]*

Title

Date *24/1/05*

Category 2 and 3

The above assessment, with amendments shown, is approved in principle.

Signed

Title

Date

Signed

Title

Date

Appendix E - Form BA

FORM 'BA' (BRIDGES)**GC/TP0356**

ELR/ Bridge No NPB/719

Appendix: 4

Issue: 1

Revision: A (Feb 1993)

CERTIFICATION FOR ASSESSMENT CHECK**Assessment Group: Jacobs Infrastructure****Bridge/Line Name: Benton Road, Ilford / Newbury Park Branch****Category of Check: 1****ELR/ Bridge No: NPB/719**

We certify that reasonable professional skill and care have been used in the assessment of the above structure with a view to securing that:

- (1) It has been assessed in accordance with the Approval in Principle (where appropriate) as recorded on Form AA approved on 24 January 2005.
- (2) It has been checked for compliance with the following principal British Standards, Codes of Practice, BRB (Residuary) Limited technical notes and Assessment standards:

BE4 - "The Assessment of Highway Bridges for Construction and Use Vehicles" Ministry of Transport, 1967 (with amendments to 1969).

BS 153: Parts 3B & 4: 1958 "Steel Girder Bridges" British Standards Institution (with amendments to 12 Sept. 1968).

List any departures from the above and additional methods or criteria adopted, with reference and justification for their acceptance.


None

Category 1

Name

Signature

Date



16/02/05

Assessor

16/2/05

Assessment Checker

28.2.05

Authorised signatory of
the firm of Consulting
Engineers to whom
Assessor/Checker is
responsible.

FORM 'BA' (BRIDGES)**GC/TP0356**

ELR/ Bridge No NPB/719

Appendix: 4

Issue: 1

Revision: A (Feb 1993)

CERTIFICATION FOR ASSESSMENT CHECKCategory 2 and 3 (Note: Category 1 check must also be signed)(a) AssessmentNameSignatureDate

Assessor

Assessment Checker

Authorised signatory of
the firm of Consulting
Engineers to whom
Assessor/Checker is
responsible.

(b) CheckNameSignatureDate

Assessor

Assessment Checker

Authorised signatory of
the firm of consulting
engineers to whom
Assessor/Checker is
responsible.

This Certificate is accepted by.....

4/3/05.

FORM 'BAA' (BRIDGES)**GC/TP0356**

ELR/ Bridge No NPB/719

Appendix: 4

Issue: 1

Revision: A (Feb 1993)

CERTIFICATION FOR ASSESSMENT CHECK**Notification of Assessment Check**

Assessment Group	Jacobs Infrastructure
Bridge Name/Road No.	Benton Road, Ilford
Line Name	Newbury Park Branch
ELR Code/Structure No.	NPB/719

The above bridge has been assessed and checked in accordance with Standards which are listed on the appended Form BA. A summary of the results of the assessment in terms of capacity and restrictions is as follows:-

STATEMENT OF CAPACITY

Internal Girders below carriageway	24tons C&U
Internal Girders below footway:	24tons C&U
Edge Girder (dead load only)	Pass
Tie rods and Jack arches	Fail

Based on an empirical assessment in accordance with Bridgeguard 3 Information Sheet 22, the external jack arches fail due to their missing tie bars. The internal jack arches are laterally restrained by the concrete infill and the adjacent jack arches and they pass the empirical assessment.

Recommended Loading Restrictions

None subjected to the installation of the tie bars to the external jack arches.

Description of Structural Deficiencies and Recommended Strengthening

- Extensive corrosion to the exposed flanges of the edge girders and first internal girders.
- Extensive corrosion to the bottom flange plates of the internal girders at the third points.
- Loss of almost all the tie straps
- Cracking in the parapets, probably due to expansive corrosion of the top flanges of the edge girders
- Damage to abutment side walls from lateral movement of edge girders.

The bridge appears to be a candidate for infilling. If the bridge is retained:

- replace tie-straps to outer girders
- remove corrosion and apply paint system to arrest further corrosion.
- Minor brickwork repairs to jack arches, parapets and wingwalls.


FORM 'BAA' (BRIDGES)**GC/TP0356**

ELR/ Bridge No NPB/719

Appendix: 4

Issue: 1

Revision: A (Feb 1993)

CERTIFICATION FOR ASSESSMENT CHECKNameSignatureDate


16/02/05 Assessor

16/2/05 Assessment Checker

20.2.05
Authorised signatory of
the firm of Consulting
Engineers to whom
Assessor/Checker is
responsible.This Certificate is accepted by...............

4/3/05.

Appendix F - Calculations




NP8/719 BENTON ROAD

CROSS-SECTION

Scale 1:50
1m 1m


BE4 Survey - Jan. 2005
Figure 1



NPB/719 BENTON ROAD
 EDGE GIRDER DETAILS
 BEA Survey Jan. 2003
 Figure 2

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 1	
Subject: NPB 719	Edge girders		Calc No: 39.1
Job No: J24110GA	BM assessment		File: R6
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:




NPB/719 BENTON ROAD
CROSS-SECTION
BE4 Survey - Jan. 2005
Figure 1

Both external girders are not loaded with traffic loading. The pedestrian pavements are wider than the spanning of the Jack arches, hence the external girders should be assessed only for dead loading.

The most corroded North edge girder will be assessed at mid span. If it is adequate for the loading then the South span by inspection is adequate to support the loading.

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 2	
Subject: NPB 719		Calc No: 39.1	
Job No: J24110GA		File: 26	
Made By:	Date: Feb 05	Revised By:	Date:
Checked By:	Date: 2/05	Checked By:	Date:



Self weight = TF = $2 \times 14 \times \frac{1}{2}$ = 14 in²

Angles = $4 \times (3\frac{1}{2} \times \frac{1}{2} + 3 \times \frac{1}{2})$ = 13 in²

Web = $27 \times \frac{3}{8}$ = 10.125 in²

BF = $2 \times 14 \times \frac{1}{2}$ = 14 in²

Total area = 51.125 in² = 0.355 ft²

Add 10% for stiffeners, bolts, rivets

BE4-1967 SW = $0.355 \times 1.1 \times 480 = 187.5 \text{ lb/ft} = 0.08 \text{ ton/ft}$ ✓

Parapet - Loading

Area = $345 \times (1710 + 681) = 824895 \text{ mm}^2 = 8.88 \text{ ft}^2$ ✓


BE4-1967 Parapet weight = $8.88 \times 140 = 1243.1 \text{ lb/ft}$ ✓

= 0.555 ton/ft ✓

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 3	
Subject: NPB 719		Calc No: 39.1	
Job No: J24110GA		File: R6	
Made By:		Date: Feb 05	Revised By:
Checked By:		Date: 2/05	Checked By:

Jack Arch



$$\left. \begin{aligned} r &= 0 + 16 \\ r^2 &= 0^2 + 24^2 \end{aligned} \right\} \Rightarrow \frac{0^2 + 16^2 + 320}{2} = \frac{0^2 + 24^2}{2} \Rightarrow$$

$$0 = \frac{24^2 - 16^2}{32} = 10 \text{ in}$$

$$\therefore r = 0 + 16 = 10 + 16 = 26 \text{ in}$$

$$\tan \phi = \frac{0}{24} = \frac{10}{24} \Rightarrow \hat{\phi} = 22.6^\circ$$

$$\hat{\theta} = 180 - (2 \times \phi) = 180 - 2 \times 22.6 = 135^\circ$$

$$\text{Area of total sector} = \hat{\theta} = \frac{135}{360} \times \pi \times r^2 =$$

$$= 797 \text{ in}^2$$

$$\text{Area } \nabla = \frac{10 \times 48}{2} = 240 \text{ in}^2$$

$$\text{Area void } \ominus \equiv \hat{\theta} - \nabla = 797 - 240 = 557 \text{ in}^2$$

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 38 4	
Subject: NPB 719		Calc No: 38 39.1	
Job No: J24110GA		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:

$$\text{Area brick} = \frac{\theta}{360} \times \pi \times (R^2 - r^2)$$

$$= \frac{135}{360} \times \pi \times ((26+8)^2 - 26^2) = 266 \text{ in}^2$$

$$= 4.01 \text{ Ft}^2$$

BE4-1967

$$\text{Ring weight} = 4.01 \times 140 = 562 \text{ lb/Ft}$$

$$= 0.25 \text{ ton/Ft}$$

Concrete Infill

✓ OK

Area of concrete jack arch infill

$$= 28" \times 62" - \text{area of sector} \quad \curvearrowright$$

$$- \text{area of ring}$$

$$= 1736 - 797 = 557$$

$$= 382.0 \text{ in}^2 = 2.6 \text{ Ft}^2$$

$$\text{Concrete infill weight} = 2.6 \times 150 = 390 \text{ lb/Ft}$$

$$= 0.17 \text{ ton/Ft}$$

Pedestrian footpath

parapet width

p.1

$$\text{Area concrete} = \frac{681}{254} \times \left(\frac{62}{2} - \frac{345}{25.4} \times \frac{1}{2} \right) = 649.1 \text{ in}^2$$

$$= 4.51 \text{ Ft}^2$$

$$\text{Footpath weight} = 4.51 \times 150 = 676.1 \text{ lb/Ft}$$

$$= 0.30 \text{ ton/Ft}$$

CALCULATION SHEET



Project Title: BE4 assessment		Sheet No: 4 5	
Subject: NPB 719		Calc No: 4 39.1	
Job No: J24110GA		File: R6	
Made By: [redacted]	Date: Feb 05	Revised By:	Date:
Checked By: [redacted]	Date: 2/05	Checked By:	Date:

Clear span of girder = 25' 3 1/2" ✓

BE4 -1967
303 a)ii)

Effective span = 25'-3 1/2" + 2 * (1/3 * 1/4 * 28")

= 308.17 in = 25.68 ft ✓

Total dead loads = 0.08 + 0.555 + 0.25/2 + 0.17/2 + 0.50 = 1.14 ton/ft

wrought iron girder
parapet
curb
footpath

M dead loads = $\frac{w L^3}{8} = \frac{1.14 \times 25.68^3}{8} = 94. \text{ ton ft}$ ✓


CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 6	
Subject: NPB 719		Calc No: 39.1	
Job No: J24110GA		File: R6	
Made By:	Date: Feb 05	Revised By:	Date:
Checked By:	Date: 2/05	Checked By:	Date:

Section properties

Mid-span

Following the descriptive external girder condition at Jacobs's "assessment and inspection report" - Feb 05



No corrosion on web and angles

	Area (in ²)	y (in)	A-y (in ³)
TF	$14 \times 1 \times 50\% = 7$	28.5	199.5
2x Angles	$2 \times 3.5 \times \frac{1}{2} = 3.5$	27.75	97.125
2x	$2 \times 3 \times \frac{1}{2} = 3$	26.0	78.0
web	$(27 - \frac{7}{8}) \times \frac{3}{8} = 9.8$	14.5	142.1
2x Angles	$2 \times (3.0 - \frac{7}{8}) \times \frac{1}{2} = 2.125$	3.0	6.375
2x	$2 \times (3.5 - \frac{3}{4}) \times \frac{1}{2} = 2.75$	1.25	3.438
BF	$(14 - \frac{9}{4}) \times \frac{1}{2} \times 80\% = 5.0$	0.75	3.75
	$(14 - \frac{9}{4}) \times \frac{1}{2} \times 30\% = 1.875$	0.25	0.469

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 7	
Subject: NPB 719		Calc No: 39.1	
Job No: J24110GA		File: R6	
Made By:	Date: Feb 05	Revised By:	Date:
Checked By:	Date: 2/05	Checked By:	Date:

$$\sum \text{AREA} = 35.05 \text{ m}^2$$

$$\sum A \times y = 530.76 \text{ m}^3$$

$$\bar{y} = 530.76 / 35.05 = 15.14 \text{ m}$$

$$I_{xx} = \sum \frac{bd^3}{12} + A \times (\bar{y} - y)^2$$

$$\text{TF} \quad = \frac{7 \times 1^3}{12} + 7(28.5 - 15.14)^2 = 1250.01$$

$$\text{Angle} \quad = 2 \times \frac{3.5 \times \frac{1}{2}^3}{12} + 3.5(27.25 - 15.14)^2 = 556.62$$

$$= 2 \times \frac{\frac{1}{2} \times 3^3}{12} + 3(26.0 - 15.14)^2 = 356.07$$

$$\text{web} \quad = \frac{3/8 \times (27 - 3/8)^3}{12} + 9.8(14.5 - 15.14)^2 = 561.22$$

$$\text{Angle} \quad = 2 \times \frac{\frac{1}{2} \times (3 - 3/8)^3}{12} + 2.125(3 - 15.14)^2 = 313.98$$

$$= 2 \times \frac{(3.5 - 3/4) \times \frac{1}{2}^3}{12} + 2.75(1.25 - 15.14)^2 = 530.62$$

$$\text{BF} \quad = \frac{(14 - 6/4) \times 80\% \times \frac{1}{2}^3}{12} + 5.0(0.75 - 15.14)^2 = 1035.46$$

$$= \frac{(14 - 6/4) \times 30\% \times \frac{1}{2}^3}{12} + 1.875(0.25 - 15.14)^2 = 415.75$$

$$I_{xx} = 5019.73 \text{ m}^4$$

$$= 0.242 \text{ ft}^4$$

$$Z_{\text{TOP}} = \frac{5019.73}{29 - 15.14} = 362.17 \text{ m}^3, \quad Z_{\text{BOT}} = \frac{5019.73}{15.14} = 331.55 \text{ m}^3$$

CALCULATION SHEET

Project Title: BE4 assessment			Sheet No: 10 8	
Subject: NPB 719			Calc No: 10 39.1	
Job No: J24110GA			File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:		Date:
Checked By: [REDACTED]	Date: 2/05.	Checked By:		Date:

p. 5

M dead loads = 94.0 ton ft

$$\text{Dead load stress, } \sigma_{DL} = \frac{M}{\text{MIN}(Z_1, Z_2)} = \frac{94.0 \times 12}{331.55}$$

$$\sigma_{DL} = 3.4 \text{ ton/in}^2 \quad \checkmark$$

EDGE GIRDER BENDING CAPACITY AT MID-SPAN

Section properties

Ref p.6

$$I_{yy_{TF}} = \frac{1 \times 7^3}{12} = 28.58$$

$$I_{yy_{ANGLES}} = \left[2 \times \frac{1/2 \times 3.5^3}{12} + 3.5 \left(\frac{3.5}{2} + \frac{3/8}{2} \right)^2 \right] \times 2 = 33.42$$

$$= \left[2 \times \frac{3 \times 1/2^3}{12} + 3 \left(\frac{1/2}{2} + \frac{3/8}{2} \right)^2 \right] \times 2 = 1.27$$

$$I_{yy_{web}} = \frac{2.7 \times (3/8)^3}{12} = 0.12$$

$$I_{yy_{BF}} = \frac{1/2 \times (14 \times 80\%)^3}{12} = 58.54$$

$$= \frac{1/2 \times (14 \times 30\%)^3}{12} = 3.09$$

$$I_{yy} = 125.02 \text{ in}^4$$

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 9	
Subject: NPB 719		Calc No: 39.1	
Job No: J24110GA		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:

The edge girder is not considered to be adequately restrained.
Hence BS:153: Part 3 B: 1958 cl 28b is applicable.

BS:153
cl 21 a)) $l = \text{span} = 25.68 \text{ ft}$

But the loading from the parapet is applied directly on the compression flange and both the load and the flange are free to move laterally.
Hence, an increase up to 20% is applied.

The % is depending on the ratio of the parapet loading to the total load.

p.5
$$\therefore \frac{\text{weight of parapet}}{\text{total loads}} = \frac{0.555}{1.14} = 0.487 \text{ or } 48.7\%$$

So we will increase the eff. span by

$$48.7\% \times 20 = 9.73\%$$

Hence, eff length of compression

$$\begin{aligned} \text{Flange for buckling} &= L + 9.73\% \times L = 25.68 \times \left(\frac{9.73}{100} + 1 \right) \\ &= 28.18 \text{ ft.} \end{aligned}$$

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 10	
Subject: NPB 719		Calc No: 39.1	
Job No: J24110GA		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By:	Date: 2/05	Checked By:	Date:

$$\begin{aligned} I_{xx} &= 5019.73 \text{ in}^4 \\ I_{yy} &= 125.02 \text{ in}^4 \end{aligned} \quad \left. \vphantom{\begin{aligned} I_{xx} &= 5019.73 \text{ in}^4 \\ I_{yy} &= 125.02 \text{ in}^4 \end{aligned}} \right\} I_{xx} > I_{yy}$$

\therefore BS 153 : 30 clause 28 b applies

$$C_s = \frac{170000}{(l/r_y)^2} \sqrt{1 + \frac{1}{20} \left(\frac{l}{r_y} \frac{T}{D} \right)^2}$$

$T \equiv$ eff. thickness of comp. Flange = 1 in

$t \equiv$ web thickness = $3/8$ in

$$\frac{T}{t} = \frac{1}{3/8} = 2.67 > 2.0 \text{ (Don't increase by 20\%)}$$

$D \equiv$ overall depth of girder = 29 in

$$r_y = \sqrt{\frac{I_{yy}}{A_{gross}}} = \sqrt{\frac{125.02}{35.05}} = 1.889 \text{ in}$$

$$l = 28.18 \text{ Ft} = 338.16 \text{ in}$$

$$\begin{aligned} \therefore C_s &= \frac{170000}{\left(\frac{338.16}{1.889} \right)^2} \sqrt{1 + \frac{1}{20} \left(\frac{338.16}{1.889} \times \frac{1}{29} \right)^2} \\ &= 9.04 \text{ ton/in}^2 \end{aligned}$$

Table 8
BS 153

P_{bc} for steel to BS 15 and BS 2762 = 3.912 ton/in^2

Table 1

Enhance, by 25%, $P_{bc} = 3.912 \times 1.25 = 4.89 \text{ ton/in}^2$

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 11	
Subject: NPB 719		Calc No: 39.1	
Job No: J24110GA		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:

cl 25
table 3

$d_1 \equiv$ distance between angles $= 27 - 2 \times \frac{1}{2} = 26$ in

$t = 3/8$ in

$$\frac{d_1}{t} = \frac{26}{3/8} = 69.3 < 75$$

hence from table 3 $\rightarrow P_{bc}' = 10 \text{ ton/in}^2$

Use the lowest value, hence

$$P_{bc} = 4.89 \text{ ton/in}^2$$

Converting P_{bc} to wrought iron value

$$P_{bc} = \frac{10.75}{16} \times 4.89 = 3.29 \text{ ton/in}^2 \quad \checkmark$$

Allowable bending moment

In tension:

$$M_{\text{tension}} = \frac{P_{bt} \times I_{xx}}{y} = \frac{8.4 \times 5019.73}{15.14} = 2785.1 \text{ ton.in} \\ = 232.1 \text{ ton.ft}$$

In compression:

$$M_{\text{comp}} = \frac{P_{bc} \times I_{xx}}{29 - 15.14} = \frac{3.29 \times 5019.73}{13.86} = 1189.9 \text{ ton.in} \\ = 99.2 \text{ ton.ft}$$

P.5

$$M_{\text{comp}} = 99.2 \text{ ton.ft} > M_{\text{dead loads}} (94 \text{ ton.ft})$$

OK


By inspection the BM capacity at $1/3$ span is adequate for the imposed loading

Project Title: BE4 assessment		Sheet No: 1	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By:		Date: Feb 05	Revised By:
Checked By:		Date: 2/05	Checked By:

Internal girders

Girders No 3 to 7 are fully loaded with live loading. The girder with the worst corrosion, according to Jacobs's report, is girder No 5. Girder No 5 will be assessed at both mid span and 1/3 span.

Section properties of girder No 5 - Mid span



		Area (in ²)	y (in)	A x y (in ³)	
Ref p. 6 calcs 39.1	TF	14 x 1 = 14	28.5	399.0	Σ AREA = 47.05 in ²
	angles	3.5	27.75	97.125	
		3.0	26.0	78.0	Σ Ay = 730.132 in ³
	web	9.8	14.5	142.1	
	angles	2.125	3.0	6.375	y = $\frac{730.132}{47.05} = 15.56 \text{ in}$
		2.75	1.25	3.438	
BF		(14 - 6/4) x 1/2 = 6.25	0.75	4.688	
		6.25 x 90% = 5.625	0.25	1.406	

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 2	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By: <u>KT</u>	Date: Feb 05	Revised By:	Date:
Checked By: <u>grr</u>	Date: 2/05	Checked By:	Date:

$$I_{xx} = \sum \frac{bd^3}{12} + A(y-y)^2$$

$$TF = \frac{14 \times 1^3}{12} + 14(28.5 - 15.56)^2 = 2345.4$$

$$Angle = 2 \times \frac{3.5 \times \frac{1}{2}^3}{12} + 3.5(27.75 - 15.56)^2 = 520.16$$

$$= 2 \times \frac{\frac{1}{2} \times 3^3}{12} + 3(26.0 - 15.56)^2 = 329.23$$

$$web = \frac{3.8 \times (27.25)^3}{12} + 9.8(14.5 - 15.56)^2 = 568.22$$

$$Angle = 2 \times \frac{\frac{1}{2} \times (3.75)^3}{12} + 2.125(3 - 15.56)^2 = 336.03$$

$$= 2 \times \frac{(0.5 - 3/4) \times \frac{1}{2}^3}{12} + 2.75(1.25 - 15.56)^2 = 563.19$$

$$BF = \frac{(14 - 6/4) \times \frac{1}{2}^3}{12} + 6.25(0.75 - 15.56)^2 = 1370.98$$

$$= \frac{(14 - 6/4) \times \frac{1}{2}^3}{12} \times 90\% + 5.625(0.25 - 15.56)^2 = 1301.43$$

$$I_{xx} = 7334.61 \text{ m}^4 \quad \checkmark$$

$$= 0.354 \text{ m}^4$$

$$Z_{TOP} = \frac{7334.61}{29 - 15.56} = 545.73 \text{ m}^3 \quad \checkmark$$

$$Z_{BOT} = \frac{7334.61}{15.56} = 471.38 \text{ m}^3 \quad \checkmark$$

CALCULATION SHEET



Project Title: BE4 assessment		Sheet No: 3	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:

Dead loading of Girder No 5

Ref p.1
calcs 39.1

Carriageway loading - Assume 100mm tarmac

$$\text{Area} = \frac{715 - 100}{25.4} \times 62 = 1501.2 \text{ m}^2 \approx 10.42 \text{ Ft}^2$$

$$\text{Fill weight} = 10.42 \times 135 = 1406.7 \text{ lb/Ft} \\ = 0.63 \text{ ton/Ft}$$

Tarmac

$$\text{Area} = \frac{100}{25.4} \times 62 = 244.1 \text{ m}^2 \approx 1.695 \text{ Ft}^2$$

$$\text{Tarmac weight} = 1.695 \times 144 = 244.1 \text{ lb/Ft} \\ = 0.11 \text{ ton/Ft}$$

Total dead loads = wrought iron SW + jack arch
+ concrete jack arch in fill + Fill material + tarmac

$$= 0.08 + 0.25 + 0.16 + 0.63 + 0.11 = 1.23 \text{ ton/Ft}$$

$$M_{\text{dead loads}} = \frac{1.23 \times 25.68^2}{8} = 101.4 \text{ tonft}$$

$$\text{Dead load stress} = \frac{101.4}{47138} \times 12 = 2.58 \text{ ton/m}^2$$

$$\text{Basic permissible stress} = 8.4 \text{ ton/m}^2$$

$$\text{Available stress for LL} = 8.4 - 2.58 = 5.82 \text{ ton/m}^2$$

$$\text{Available Moment for LL} = 5.82 \times 47138 = 2742.9 \text{ toni.} \\ = 228.6 \text{ tonft}$$


CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 4	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:

Live loading

The quick assessment method as indicated in Part II section 3 is applicable according to BE4 - d 303 (c) for jack arches and zero skew bridge.

Since carriageway width = 8.17 m \approx 26.8 ft > 18 ft, the double lane graphs are applicable ✓



$$\text{span} = 25.6 \text{ ft}$$

$$\text{girder spacing} = 62" = 5.16 \text{ ft}$$

using graph No 2

$$K = 0.53$$


$$LL \text{ Moment} = \frac{\text{Available moment } LL}{K}$$

$$= \frac{228.6}{0.53} = 431.3 \text{ ton F}$$

CALCULATION SHEET



Project Title: BE4 assessment		Sheet No: 5	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:



From graph No 5
 \therefore Gross vehicle weight is
 24 tons (full standard)

OK

Girder assessed bbl Resistance = $8.4 \times \frac{431.38}{12} = 330 \text{ ton Ft}$

Full Card U load effect = $137 \text{ ton Ft} \times 0.53 = 72.6 \text{ ton Ft}$

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 6	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By:	Date: Feb 05	Revised By:	Date:
Checked By:	Date: 2/05	Checked By:	Date:

Internal girder - $\frac{1}{3}$ span -

There is plenty capacity (see p.5) from graph 5 for the mid-span bending moments. By inspection, the girder with only 20% extra corrosion on the bottom $\frac{1}{2}$ " plate can be assessed as adequate for the 24 ton loading. An approximate and conservative approach could be adopted by assuming that the corroded section exists at mid span instead.

Ref p.1

$$BF \quad 6.25 \times 70\% = 4.375 \text{ m}^2$$

$$y = 0.25 \rightarrow Ay = 1.094 \text{ m}^3$$

$$\bar{y} \equiv \text{remains almost unchanged} = 15.56 \text{ in}$$

$$I_{xx} \text{ OF} = \frac{(14 - 6/4) \times 1/2^3}{12} \times 0.7 + 4.375 (0.25 \times 15.56)^2 = 1026 \text{ m}^4$$

$$I_{xx} \text{ TOTAL} = 7334.61 + 1026 - 1301.43 = 7059 \text{ m}^4$$

$$Z_{TOP} = \frac{7059}{29 - 15.56} = 525.2 \text{ m}^3$$

$$Z_{BOT} = \frac{7059}{15.56} = 453.7 \text{ m}^3$$

"The difference is less than $5\frac{1}{2}$ "

CALCULATION SHEET



Project Title: BE4 assessment		Sheet No: 7	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:

$$\text{Dead load stress} = \frac{90.4^*}{453.7} \times 12 = 2.39 \text{ ton/in}^2 \quad \checkmark$$

permissible stress

$$\text{Available moment for LL} = (8.4 - 2.39) \times 453.7$$

$$= 2726.3 \text{ ton.in}$$

$$= 227.2 \text{ ton.ft} \quad \checkmark$$

Ref p.4

$$K = 0.53 \rightarrow \text{LL Moment} = \frac{227.2}{0.53} = 428.7 \text{ ton.ft} \quad \checkmark$$

From graph No. 5 \therefore The girder can support full (24 tons) standard traffic loading \checkmark

*

$$\text{Reaction} = \frac{1.23 \times 25.68}{2} = 15.8 \text{ ton}$$


$$M \text{ at } 1/3 \text{ span (at } 8.6\text{m)} = 15.8 \times 8.6 - \frac{1.23 \times 8.6^2}{2}$$

$$= 90.4 \text{ ton.ft} \quad \checkmark$$

Project Title: BE4 assessment		Sheet No: 8	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By:		Date: Feb 05	Revised By:
Checked By:		Date: 2/05	Checked By:

1st internal girder (South)

The 1st internal girder (South side) is reported with 55% corrosion at the bottom flange at the midspan and 1/3 span. Section properties from p.1 remain unchanged except for the BF



Area (in ²)	y (in)	A y (in ³)
BF 1 st = 6.25 × 45% = 2.8125	0.75	2.11
2 nd plate = 2.8125	0.25	0.70

Σ AREA = 40.8 in²

Σ AY = 726.85 in³

$\bar{y} = \frac{726.85}{40.8} = 17.8 \text{ in}$

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 9	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:

$$I_{xx} = \sum \frac{bd^3}{12} + A(y-\bar{y})^2$$

$$TF = \frac{14 \times 1^3}{12} + 14(28.5 - 17.8)^2 = 1604.0$$

$$Angle = 2 \times \frac{3.5 \times \frac{1}{2}^3}{12} + 3.5(29.75 - 17.8)^2 = 346.6$$

$$= 2 \times \frac{\frac{1}{2} \times 3^3}{12} + 3.0(26 - 17.8)^2 = 203.97$$

$$web = \frac{3/8 \times (27 - 7/8)^3}{12} + 9.8(14.5 - 17.8)^2 = 663.9$$

$$Angle = 2 \times \frac{\frac{1}{2} \times (3 - 9/8)^3}{12} + 2.125(3 - 17.8)^2 = 466.3$$

$$= 2 \times \frac{(3.5 - 3/4) \times \frac{1}{2}^3}{12} + 2.75(12.5 - 17.8)^2 = 753.3$$

$$BF = \frac{(14 - 6/4) \times 45\% \times \frac{1}{2}^3}{12} + 2.8125(0.75 - 17.8)^2 = 817.7$$

$$= \frac{(14 - 6/4) \times \frac{1}{2}^3 \times 45\%}{12} + 2.8125(0.25 - 17.8)^2 = 866.3$$


$$I_{xx} = 5722 \text{ in}^4$$

$$Z_{TOP} = \frac{5722}{29 - 17.8} = 510.9 \text{ in}^3$$

$$Z_{BOT} = \frac{5722}{17.8} = 321.5 \text{ in}^3$$

Project Title: BE4 assessment		Sheet No: 10	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By:		Date: Feb 05	Revised By:
Checked By:		Date: 2/05	Checked By:
		Date:	
		Date:	

Loading effects



The traffic loading is spread equally to both 1st and 2nd internal girders (conservative)

The dead loading on the 1st internal girder is similar to the edge girder

Hence

p.5
calcs 39.1

$$DL = SW + brickwork + concrete fill + Footpath \\ = 0.08 + 0.25 + 0.16 + 0.77 = 1.26 \text{ ton/ft}$$

calcs 39.1
p.4

$$W_{Footpath} = \frac{681}{25.4} \times 62 \times \frac{1}{12^2} \times 150 = 1731.5 \text{ lb/ft} \approx 0.77 \text{ ton/ft}$$

CALCULATION SHEET

Project Title: BE4 assessment		Sheet No: 11	
Subject: NPB 719		Calc No: 39.2	
Job No: J24110GA		File: R6	
Made By:		Date: Feb 05	Revised By:
Checked By:		Date: 2/05	Checked By:
		Date:	

$$M \text{ dead loads} = \frac{1.26 \times 25.68^2}{8} = 103.9 \text{ ton ft}$$


$$\text{Dead load stress} = \frac{103.9}{321.5} \times 12 = 3.88 \text{ ton/in}^2$$

$$\text{Basic perm. stress} = 8.4 \text{ ton/in}^2$$

$$\text{Available stress for LL} = 8.4 - 3.88 = 4.52 \text{ ton/in}^2$$

$$\text{Available moment for LL} = 4.52 \times 321.5 = 1454 \text{ ton in} \\ = 121.2 \text{ ton ft}$$

Treat the girder as an external girder since it's only loaded with ~~50%~~ part of the traffic loading.



DOUBLE LANE GRAPH No. 4.

Girders spacing.

Ref P. 4

$$\text{span} = 25.6 \text{ ft}$$

$$\text{Girders spacing} = 5.16 \text{ ft}$$

$$K = 0.495$$

\therefore LL Moment

$$= \frac{121.2}{0.495}$$

$$= 244.8 \text{ ton ft}$$

From graph No. 5
Ref P. 5

\therefore Gross vehicle weight is

$$244 \text{ tons (full standard)}$$

and over
For angles of skew greater than 35° multiply factors by 1.15

CALCULATION SHEET

Project Title: BE4 assessment			Sheet No: 1	
Subject: NPB 719	Shear Stress Calculations		Calc No: 39.3	
Job No: J24110GA	Internal Girders		File: R6	
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:	
Checked By: [REDACTED]	Date: 2/05	Checked By:	Date:	

From BS 153: Part 38: 1958, table 3
(Parts in shear), the average permissible
shear stress is $F_q = 6.0 \frac{\text{ton}}{\text{in}^2}$

Enhanced stress $= 6.0 \times 1.25 = 7.5 \text{ ton/in}^2$
Converting F_q to wrought iron value

$$\therefore F_q = 7.5 \times \frac{10.75}{16} = 5.04 \text{ ton/in}^2$$

cl 29a
Part 38
BS 153

$$P_q = 6 \left[1.3 - \frac{b/t}{250 \left(1 + \frac{1}{2} \left(\frac{b}{a} \right)^2 \right)} \right]$$

$$a = 29 - 2 \times \frac{1}{2} = 28 \text{ in} < (270t) = 101.25 \text{ in}$$

$$b = 28 \text{ in} < (180t) = 67.5 \text{ in}$$

$$\text{hence } P_q = 6 \left[1.3 - \frac{28/318}{250 \left(1 + \frac{1}{2} \times 1^2 \right)} \right]$$

$$= 6.61 \text{ ton/in}^2$$

(Conservatively we ignored the effect of the stiffeners on the girders)

$$F_q < P_q, \text{ hence use } F_q = 5.04 \text{ ton/in}^2$$

CALCULATION SHEET



Project Title: BE4 assessment		Sheet No: 2	
Subject: NPB 719	Shear Stress Calculations		Calc No: 39.3
Job No: J24110GA	Internal Girder		File: R6
Made By: [REDACTED]	Date: Feb 05	Revised By:	Date:
Checked By:	Date: 2/05	Checked By:	Date:

Dead load reaction at supports

$$= \frac{1.25 \times 25.68}{2} = 15.8 \text{ ton}$$

P. 3
calcs 39.2

shear stress on girder web

$$q = \frac{R}{A} = \frac{15.8}{t \times b} = \frac{15.8}{\frac{3}{8} \times 27} = 1.56 \text{ ton/in}^2$$

Available shear stress for live loading

$$= 5.04 - 1.56 = 3.48 \text{ ton/in}^2$$

$$\text{Capacity} = 3.48 \times 10.125 = 35.2 \text{ tons}$$

$$A = t \times b = \frac{3}{8} \times 27 = 10.125 \text{ in}^2$$

BE4:1967
Part I
305 a)
Table 1

Compare the available live load capacity to the values from table 1

Table 1

Span ft	Shear Value Tons
15 and below	10
20	11
25 25.68 ft	11.64
30	12.5
35	14
40	15.5
50	17.5
60	20.5

Live load shear stress capacity inner beam

$$= 35.2 \text{ ton} > \text{Live load effect} = 11.60 \text{ ton}$$

on

Project Title: BE4 assessment		Sheet No: 3	
Subject: NPB 719	Shear Stress Calculations		Calc No: 39.3
Job No: J24110GA	Parapet girders		File: R6
Made By: [redacted]	Date: Feb 05	Revised By:	Date:
Checked By: [redacted]	Date: 2/05	Checked By:	Date:

The parapet girders by inspection are adequate for the shear stresses induced by the parapet loading, since the dead loading of the parapet girder is less than the DL of the inner girders. Also the 1st internal girders carry only part of the traffic loading and therefore by inspection are adequate to withstand the shear stresses.

It should be noted that no corrosion on the web was recorded.

PRO FORMA FOR EMPIRICAL ASSESSMENT OF BRICK, MASONRY AND CONCRETE JACK ARCHES AND ASSOCIATED TIES
(To be included with the Assessment Report Calculations)

BRIDGE NAME:	Benton Road / Newbury Park Branch
RAILTRACK NO:	NPB 719

Assessment should include completion of all three Sections even where Section 1 has shown the bridge deck to be non-compliant.

SECTION 1 CHECKS FOR COMPLIANCE WITH 24 T CONFIGURATION REQUIREMENTS

	Compliant Yes/No
What is maximum clear span of the arch <i>Non-compliant if greater than 2.0m</i>	1.575 m <u>Yes</u>
Do jack arches spring from bottom flanges of beams? <i>If not, non compliant</i>	Y <u>Yes</u>
What is the beam spacing? What is the rise of the arch? Gross aspect ratio <i>Non-compliant if greater than 10</i>	$b := 1.219 \text{ m}$ $r_c := 0.406 \text{ m}$ $\frac{b}{r_c} = 3.002$ <u>Yes</u>
What is the arch barrel thickness (including concrete fill above) and how is it derived ie from record drawings or site investigation? <i>Non-compliant if thickness less than 220</i>	$d := 305 \text{ mm}$ Site investigation <u>Yes</u>

SHEET No.	1
CALC No.	39.4
FILE	R6
JOB No.	J241106A
MADE BY	
CHECKED BY	

PRO FORMA FOR EMPIRICAL ASSESSMENT OF BRICK, MASONRY AND CONCRETE JACK ARCHES AND ASSOCIATED TIES
 (To be included with the Assessment Report Calculations)

BRIDGE NAME:	Benton Road / Newbury Park Branch
RAILTRACK NO:	NPB 719

Assessment should include completion of all three Sections even where Section 1 has shown the bridge deck to be non-compliant.

SECTION 2 CHECKS FOR DEFICIENCY

Type No	Deficiency	Pass/Fail
1	<p>What is the backing material? Is it structural? concrete (friable) ✓</p> <p>Does the structural backing extend to at least the crown level of the arch extrados? ✓</p> <p style="text-align: right;"><i>If not, then fail (1) (4)</i></p> <p>Height of structural fill above crown $d_f := 715 \text{ mm}$</p> <p>What is effective shear depth of deck?</p> <p>(= arch rise + barrel thickness + depth of structural fill above crown of extrados)</p> <p>$D_s := r_c + d + d_f$ $D_s = 1.426 \cdot 10^3 \text{ mm}$ ✓</p> <p>Is $D_s \geq$ "minimum requirements of Fig 1 " Fail if $<$ Fig 1</p> <p style="text-align: center;">$\alpha = 450 \text{ mm} < D_s$ \Rightarrow</p> <div style="text-align: center;"> </div>	<p><u>Yes</u></p> <p><u>Yes</u></p> <p><u>Pass</u></p>

Figure 1

SHEET No 2
 CALC No 39.4
 FILE R6
 JOB No J24110GA
 MADE BY [REDACTED]
 CHECKED BY [REDACTED]

2	<p>Do jack arches span longitudinally (eg in half through girder construction) or transversely between longitudinal girders? <u>-Transversely-</u> ✓</p> <p>For longitudinal spanning jack arches, ignore following questions on ties/lateral restraint and state N/A.</p> <p>Are ties provided in edge bays of transversely spanning jack arches? <u>No</u> ✓</p> <p><i>If yes, go to 3a/3b If not, fail unless edge bay is 'hard' (see 5)</i></p>	<u>Fail</u> ✓
3a CI	<p>What is the cross sectional area of one tie? (allowing for corrosion losses) Diameter of tie <u>Dia := 1 mm</u></p> <p>Therefore Area $A := \pi \frac{(Dia)^2}{4}$ $A = 0.785 \text{ mm}^2$</p> <p>What is number of ties per beam length? <u>n := 2</u></p> <p>What is the clear skew span? <u>L := 1 m</u></p> <p>Specific area of tie $A_s := \frac{(n+1) \cdot A}{L}$ $A_s = \frac{1.57 \text{ mm}^2}{1 \text{ m}}$</p> <p><i>Non-compliant if less than 260mm²/m</i></p> <p>What is maximum tie spacing? <u>S := 1 m</u></p> <p><i>Non-compliant if greater than 2.5m for cast iron</i></p>	
3b WI/ST	<p>What is the cross sectional area of one tie? (allowing for corrosion losses) Dimensions of the tie <u>dt1 := 1 mm</u> <u>dt2 := 1 mm</u></p> <p>Therefore Area $A := dt1 \cdot dt2$ $A = 1 \text{ mm}^2$</p> <p>What is number of ties per beam length? <u>n := 4</u></p> <p>What is the clear skew span? <u>L := 8.04 m</u></p> <p>Specific area of tie $A_s := \frac{(n+1) \cdot A}{L}$ $A_s = \frac{5 \text{ mm}^2}{8.04 \text{ m}}$</p> <p><i>Non-compliant if less than 260mm²/m</i></p> <p>What is maximum tie spacing? <u>S := 1 m</u></p> <p><i>Non-compliant if greater than 3.0m for wrought iron/steel</i></p>	
4	<p>Are ties located within crown of external arch?</p> <p><i>If so, then fail CI or possible fail for WI/steel</i></p>	
5	<p>Does external bay construction provide alternative lateral restraint? (ie not soft edge)?</p> <p><i>If so, pass. If not, are ties provided in first Jack Arch bay? If yes, treat as 3a (or 3b). otherwise fail.</i></p>	<u>No</u> ✓

Notes: (1) Results also in loss of D/d (composite action) for cast iron beams
(4) A trial hole should be undertaken to confirm the existence of structural backing if there is any doubt.

SHEET No	3
CALC No	39.4
FILE	R6
JOB No	3241106A
MADE BY	
CHECKED BY	

PRO FORMA FOR EMPIRICAL ASSESSMENT OF BRICK, MASONRY AND CONCRETE JACK ARCHES AND ASSOCIATED TIES
(To be included with the Assessment Report Calculations)

BRIDGE NAME:	Benton Road / Newbury Park Branch
RAILTRACK NO:	NPB 719

Assessment should include completion of all three Sections even where Section 1 has shown the bridge deck to be non-compliant.

SECTION 3 CHECKS FOR DEFICIENCY

Type No	Defect	Empirical Assessment		Pass/Fail
		CI Decks	WI/Steel Decks	
6	Rotation of supporting beam	Fail	Fail	No indication
7	Horizontal displacement of supporting beam <u>Dispaced brickwork indicating displacement of the edge girders due to missing ties</u>	Fail	Fail	<u>Fail</u>
8	Inadequate support to springings eg corrosion of bottom flange of supporting beam over a significant length, missing bedding mortar	Possible Fail	Possible Fail	Possible Fail
9	Transversely bowed bottom flange of supporting beam	Fail	Fail	No indication
10	Cracking at crown of arch owing to spreading of springings (other than 12, 13)	Fail	Fail	No indication
11	Distortion and any associated cracking of jack arch barrel	Fail	Fail	No indication
12	Arch crack resulting in substructure crack	Fail	Fail (5)	No indication
13	Substructure crack or other distress resulting in crack to jack arch	Possible Fail (3)	Possible Fail (3) (5)	No indication

Notes: (3) 'Substructure renovation' or 'Monitoring' as appropriate; 'Repair of arch' (if appropriate)
 (5) Not applicable in general to longitudinally spanning arches.

SHEET No	4
CALC No	
FILE	
JOB No	
MADE BY	
CHECKED BY	